

# Cardington Large Building Test Facility

## Construction details for the first building

by P N R Bravery

### Summary

This report details all structural information concerning the steelwork framed building erected on the Cardington strong floor during 1993. It includes, where available, test results for elements and materials used in the building and describes construction methods, specifications and standards adhered to. Extensive reference is made to construction drawings, all of which are reproduced at A3 scale within the report but the originals can be accessed via consultation with the LBTF Steering Group.

## **Contents:**

### **1. Introduction**

- 1.1 Hypothetical Location and Occupancy
- 1.2 Outline Geometry

### **2. Phase 1: Frame**

- 2.1 Structural Steelwork
- 2.2 Bracing
- 2.3 Windposts
- 2.4 Decking

### **3. Joints and Connections**

- 3.1 Nuts, Bolts and Washers
- 3.2 Column Bases
- 3.3 Column to Column splices
- 3.4 Column to Beam Connections
- 3.5 Beam to Beam Connections
- 3.6 Bracing Connections
- 3.7 Windpost Fixings
- 3.8 Statement on Robustness/Accidental Damage

### **4. Phase 2A: Composite Floors**

- 4.1 Shear Studs
- 4.2 Reinforcement Mesh
- 4.3 Concrete

### **5. Phase 2B: Walls and Partitions**

- 5.1 Blocks and Mortar
- 5.2 Blockwork Ties
- 5.3 Dado and Head Restraint
- 5.4 Partitions

**Drawings**

**Tables**

**Figures**

**Sketches**

**Appendices**

**Drawings:**

A3 copies of construction drawings for the first building

**Tables:**

1:	Lackenby steelwork testing results
2:	Shelton steelwork testing results (356*171*51UB)
3:	Shelton steelwork testing results (254*254*89UC)
4:	Scunthorpe steelwork testing average results
5:	Mill releases results for members marked with cast numbers only
6:	Average results of Nut and Bolt testing
7:	Column base plate details
8:	Specification of column splices
9:	Location and type of splice per column
10:	Standard column to beam connection details
11:	Standard beam to beam connection details
12:	Second floor transfer structure beam to beam connection details
13:	Primary beam connections at roof level
14:	Average results of reinforcement mesh testing
15:	Average 7 & 28 day cube crushing strength of concrete from the floors

**Figures:**

1 - 8	Steelwork testing member identification floor plans
9 - 17	Steelwork testing member identification elevations

**Sketches:**

SK1 BRE	Windpost fixing details gridlines A and F
SK2 BRE	Windpost fixing details gridlines 1 and 4

**Appendices:**

A	Complete list of LBTF drawings held by the Steering Group
B	Details of rolling mill test procedure

## 1. Introduction

The steelwork structure, the first to stand on the strong floor, is designed to be typical of modern multi-storey office blocks.

### 1.1 Hypothetical Location and Occupancy

The building is hypothetically located in Croydon and inhabited by a high-profile firm of lawyers employing 318 people. The usage per floor would be as follows:

Ground Floor	Reception, Personnel, Accounts, Delivery and Security
1st Floor	Library, Archives and Meeting rooms
2nd - 6th Floors	Fee-earning Offices
7th Floor	Restaurant, including kitchen
Roof	Plant and Lift gear

Each fee-earning floor would include both open plan and enclosed office space, filing and storage areas, coffee making facilities and of course toilets.

### 1.2 Outline Geometry

The building has a foot print area 21m by 45m and stands to a height of 33m. Along the length, there are 5 bays each of 9m width. The ends comprise of 3 bays, of 6m, 9m and 6m respectively. There are 8 storeys, from the first floor to the roof the top-of-steel (t.o.s.) to top-of-steel height is 4.135m, the ground floor to first floor t.o.s. distance is 4.335m.

There is a two storey 9m by 8m ground floor atrium in the central bay of the South elevation. At the West end of the building there are two voids, one 2m by 4.5m being a goods lift for the 'restaurant', and the other 4m by 4.5m, a fireman's access and escape stairwell. There is only one void at the East end of the building, the 4m by 4.5m escape stairwell. In addition to these, there is a 9m by 2.5m central lift core.

## 2. Phase 1: Frame

### 2.1 Structural Steelwork

Design of the structure was carried out by Peter Brett Associates (PBA) to BS 5950. All steel members in the structure were tested and graded to BS 4360 and were blast cleaned but not painted. For steel section sizes and arrangement see Steel Layout Drawings numbers 5992/01, 02, 03, 04 & 07 issued by PBA.

It was intended that all of the members would be rolled at British Steels' Scunthorpe mill and that each bar rolled would be tested three times. Unfortunately due to a misunderstanding within British Steel this was not the case and the work was split between three mills, Lackenby, Shelton and Scunthorpe. Each mill devised its own testing procedure and member identification scheme. Details of these arrangements have been supplied by John Dowling of British Steel and are reproduced in Appendix B, a summary of which follows:

#### Lackenby

Each batch of the same section size from the same cast were tested just once and hence the results from this mill are no more accurate than the release certificates. The members are identified by a six digit number occasionally accompanied by a single letter suffix denoting multiple members from the same bar. The test results are displayed in Table 1.

Example member identification number 737723A

#### Shelton

The columns and beams rolled at this mill were treated separately but follow the same pattern. A sample was taken from the back of the first bar and the front of the last bar rolled from each bloom. Each bar within each bloom has been identified with a letter after the bloom number, where a bar has been split into multiple members a suffix number distinguishes them. The results for the bars tested are displayed in Tables 2 and 3, best estimates of intermediary bar strengths can be interpolated from these results.

Example member identification number 11D

#### Scunthorpe

This mill carried out the most comprehensive testing, each bar from each bloom being tested three times. A three digit identifier was used and pointed on each member, the vast majority of which were identifiable on site. The results are displayed in Table 4.

Example member identification number 525

The splitting of the order added further complications in tracing the members through the mill, the testing and into the structure. Many of the identifying markings were neglected, not recorded or obscured during erection and hence coverage is patchy. Members which have been traced from the mills into the structure are marked with their identifying number on figures 1 to 17 and a question mark is used to denote absent or unclear markings.

On these figures, those numbers for which a test result is available are highlighted in red. Where an estimate of the strength can be made from an interpolation of other results for the same bar the number is highlighted in green. For a small number of beams, where the cast number is marked on the member, the mill release certificate gives the best estimate of the strength and these are marked in yellow. The results for such members are summarised in Table 5. Where no test results can be found nor valid estimates made, no highlighting has been used.

In all cases, samples were taken from the flange either side of the web/flange interface.

## 2. Phase 1: Frame

### 2.1 Structural Steelwork

Design of the structure was carried out by Peter Brett Associates (PBA) to BS 5950. All steel members in the structure were tested and graded to BS 4360 and were blast cleaned but not painted. For steel section sizes and arrangement see Steel Layout Drawings numbers 5992/01, 02, 03, 04 & 07 issued by PBA.

It was intended that all of the members would be rolled at British Steels' Scunthorpe mill and that each bar rolled would be tested three times. Unfortunately due to a misunderstanding within British Steel this was not the case and the work was split between three mills, Lackenby, Shelton and Scunthorpe. Each mill devised its own testing procedure and member identification scheme. Details of these arrangements have been supplied by John Dowling of British Steel and are reproduced in Appendix B, a summary of which follows:

#### Lackenby

Each batch of the same section size from the same cast were tested just once and hence the results from this mill are no more accurate than the release certificates. The members are identified by a six digit number occasionally accompanied by a single letter suffix denoting multiple members from the same bar. The test results are displayed in Table 1.

Example member identification number 737723A

#### Shelton

The columns and beams rolled at this mill were treated separately but follow the same pattern. A sample was taken from the back of the first bar and the front of the last bar rolled from each bloom. Each bar within each bloom has been identified with a letter after the bloom number, where a bar has been split into multiple members a suffix number distinguishes them. The results for the bars tested are displayed in Tables 2 and 3, best estimates of intermediary bar strengths can be interpolated from these results.

Example member identification number 11D

#### Scunthorpe

This mill carried out the most comprehensive testing, each bar from each bloom being tested three times. A three digit identifier was used and pointed on each member, the vast majority of which were identifiable on site. The results are displayed in Table 4.

Example member identification number 525

The splitting of the order added further complications in tracing the members through the mill, the testing and into the structure. Many of the identifying markings were neglected, not recorded or obscured during erection and hence coverage is patchy. Members which have been traced from the mills into the structure are marked with their identifying number on figures 1 to 17 and a question mark is used to denote absent or unclear markings.

On these figures, those numbers for which a test result is available are highlighted in red. Where an estimate of the strength can be made from an interpolation of other results for the same bar the number is highlighted in green. For a small number of beams, where the cast number is marked on the member, the mill release certificate gives the best estimate of the strength and these are marked in yellow. The results for such members are summarised in Table 5. Where no test results can be found nor valid estimates made, no highlighting has been used.

In all cases, samples were taken from the flange either side of the web/flange interface.

## 2.2 Bracing

### 2.2.1 Vertical Bracing

Simple vertical bracing is provided around the central lift core and the escape stairwells, see Steel Layout Drawings numbers 5992/01, 02, 03, 04 & 07 issued by PBA. Flat, grade 50 steel is used throughout and is fixed coincident with the column centre line. From the ground to 4th floor the plates are 250mm wide by 15mm thick and from the 4th floor to the roof, 200mm by 10mm.

### 2.2.2 Horizontal Bracing

Horizontal bracing is provided in the bays adjacent to the atrium at first and second floor levels. Grade 50 steel, 168.3mm diameter, 10mm thick CHS's are used and their locations can be found on drawings 5992/02 & 03 issued by PBA.

## 2.3 Windposts

Windposts are RSA's of 43B steel at 3m centres ground to 4th floor and 2.25m centres to roof. See Elevation on gridline A drawing number 5992/06 issued by PBA. The mill release certificates for these elements indicate that they have a yield stress of 280 N/mm<sup>2</sup> and a tensile strength of 459 N/mm<sup>2</sup>. A test on a specimen of length  $L_0=5.65\sqrt{S_0}$  produced a 39% elongation.

## 2.4 Decking

The decking was designed to BS 5950 part 4 using PMF CF70 sheets of 0.9mm thickness which are notched around columns as necessary. See Decking layout drawings R1112/01, 02, 03 & 04 issued by Composite Profiles. The decking is continuous over a minimum of two spans and arranged such that troughs rest along the length of beams wherever present. The sheets are shot fired to the supporting steel.

### 3 Joints and Connections

All connections were designed using the SCI/BCSA method "Joints in Simple Construction" by Caunton Engineering Ltd (CEL). A copy of the connection design calculations can be found in the 'LBTF Data 2 File'.

#### 3.1 Nuts, Bolts and Washers

A sample of the nuts, bolts and washers used were tested to BS 4395 or BS 3692 by Cooper & Turner, a summary of the results is shown in Table 6.

#### 3.2 Column Bases

Column to baseplate connections are full profile continuous fillet welds and all baseplates are of grade 43 steel. The dimensions of the baseplates vary according to column size and location, see drawings 5992/01, 03 and 05 issued by PBA. Table 7 is a schedule of all baseplate details.

For columns bearing onto the strong floor, all hold-down bolts and sockets are fixed into the reinforced concrete slab by anchor grout and the underside of the baseplate grouted up to a maximum depth of 50mm. The completed baseplate connections are cased in concrete with 75mm cover.

Columns C2 and D2 bear onto the second floor transfer structure. The hold down bolts are connected through the base plate, the 15mm thick stiffening plate and the flange of the supporting member.

#### 3.3 Column to Column splices

Internal column splices are located with the column neutral axis coincident and co-linear. External column splices are orientated such that external faces are flush. The columns around the central lift core are spliced with web and flange plates, all others use a cap and base plate splice. Table 8 details the different types of splice used and Table 9 gives a schedule of their location.

##### 3.3.1 Cap and base plate splices

Full profile, 6mm fillet welds are used to attach cap and base plates to column ends. All such end plates are of grade 43 steel and all bolts are M20 grade 8.8.

##### 3.3.2 Web and flange plate splices

Bolts through the web plate are M20 grade 8.8 and those through the flange plate are M20 general grade HSF8 bolts.

#### 3.4 Column to Beam Connections

Column to beam connections are standard on all floors except the second floor transfer structure and roof connections where a beam is continuous over a column top. See drawing numbers 5992/03 and 07 issued by PBA for the location of these exceptions.

##### 3.4.1 Standard column to beam connections

A standard connection uses flexible end plates of grade 43 steel and grade 8.8 bolts, the thickness of plate, size of fillet weld and number of bolts used in each connection is listed in Table 10.

Although listed separately, it is of note that the column size is not important when determining the type of connection used, for example, a 610\*229\*101UB has the same



connection to a 254\*254\*89UC as it does to a 305\*305\*198UC. Each column type is listed separately for clarity.

#### 3.4.2 Second floor transfer structure beam to column connections

Details of the structure necessary to transfer the loads over the two storey Atrium can be found in drawing number 5992/05 issued by PBA.

The 686\*254\*170UBs are fixed to the 305\*305\*198UCs in the following way. A 20mm thick grade 50 steel plate is welded across the toes of the column using a 8mm fillet weld to the rear of the plate and an 12mm weld to the front. The beam flanges are removed as necessary and the web bolted to the toe plate with 20 M24 grade 12.9 bolts.

At these column locations, longitudinal beams are fixed to the web of the 686\*254\*170UB, hence these east-west connections are described in the Beam to Beam connection section.

#### 3.4.3 Continuous beam to column connections at roof level

Where a beam is continuous over a column top, 15mm thick, full depth stiffeners are attached to both sides of the beam in such a way as to continue the line of the column flanges. The plates are fixed to the web and flange with 6mm fillet welds. The column is fitted with a 20mm thick cap plate also attached with a fillet weld and the beam flange is bolted to the cap plate with four M20 grade 8.8 bolts.

In these cases, longitudinal primary beams are fixed to the continuous roof beam and not the column, hence these east-west connections are detailed in the Beam to Beam connection section.

### 3.5 Beam to Beam Connections

Beam to beam connections are standard on all floors except the second floor transfer structure and roof connections where a beam is continuous over a column top. See drawing numbers 5992/03 and 07 issued by PBA for the location of these exceptions.

#### 3.5.1 Standard beam to beam connections

A standard beam to beam connection incorporates fin plates of grade 43 steel welded to the beam web only and M20 grade 8.8 bolts. The thickness of plate, size of fillet weld and number of bolts used in each connection is listed in Table 11.

#### 3.5.2 Second floor transfer structure beam to beam connections

There are three different connection types to the 686\*254\*170UB transfer beam and the details are listed in table 12. A diaphragm comprising of a short length of 356\*171\*45UB is provided at the intersection of the twin transfer beams and the two 305\*165\*40UBs (grid ref. C1/2 and D1/2).

#### 3.5.3 Continuous beam to beam connections at roof level

The connection of the longitudinal primary beams to the continuous roof beams is made in one of two ways. Firstly a toe plate is welded between the web stiffeners of the continuous member and then, either a fin plate is welded to this toe and the beam is attached to the fin plate in the standard way, or an end plate is fitted to the supported beam which is then bolted direct to the toe plate. The style of connection, the thickness of toe, fin and end plates, the size of fillet welds and the number of bolts used is detailed in Table 13.

### 3.6 Bracing Connections

#### 3.6.1 Horizontal Bracing

Each end of the CHS bracing member is fixed with 10mm thick end and gusset plates. The gusset plate is set 150mm into the end of the tube and fixed with a 6mm fillet weld. A similar gusset plate is fixed to the column with a 8mm fillet weld. The two plates are bolted together with six M20 grade 8.8 bolts.

#### 3.6.2 Vertical Bracing

From the ground to fourth floor, 15mm thick gusset plates are attached at the intersection of beam and column. A 6mm fillet weld fixes the gusset plate to both the beam flange and the oversized end plate used in the beam-column connection. The flat bracing member and gusset plate are bolted together with nine M20 grade 8.8 bolts.

From the fourth floor to the roof, 10mm thick gusset plates are used and six M20 grade 8.8 bolts are sufficient to make the connection between the flat bracing member and gusset plate.

### 3.7 Windpost Fixings

A rigid connection is made between the windpost and beam at floor level. At ceiling level, slotted holes in the windpost allow unhindered displacement of the ceiling beam, see sketches SK1 BRE and SK2 BRE originally produced by PBA.

### 3.8 Statement on Robustness/Accidental Damage

The structure as a whole will be designed in accordance with cl. 2.4.5.3 of BS 5950 Part 1 to cater for robustness and accidental damage. This approach is normally deemed to satisfy the requirements of clause A3/4 of the building regulations.

The twin transfer beams at second floor level have been classified as key elements, since their removal cannot be catered for by alternative load paths.

The transfer beams together with the supporting columns will be designed to withstand a blast loading of  $34 \text{ kN/m}^2$ .

Members required as restraints to the transfer beams and columns have also been designed as key elements ( $34 \text{ kN/m}^2$ ) to satisfy cl. 2.4.5.5. Elements supporting these restraint members in turn, have **NOT** been designed as key elements - compliance with cl. 2.4.5.3 is considered sufficient in these cases.

For reference purposes all key elements have been identified by the symbol '+' on structural drawings (5992/01 - 03 inclusive).

#### 4. Phase 2 - Floors

A Composite Floor solution was adopted including shear studs, reinforcing mesh and Lytag concrete. The completed system gives an overall floor depth of 130mm with a fire rating of 1½ hours. For composite floor details see Drawing no. 5992/05 issued by PBA.

##### 4.1 Shear Studs

The 95mm long 19mm diameter shear studs have a minimum yield stress of 350 N/mm<sup>2</sup>. They are welded through to the support beams in accordance with SCI booklet "Good practice in composite floor construction". The arrangement of shear studs is shown on drawing numbers 5992/01, 02, 03, 04 & 07 issued by PBA.

##### 4.2 Reinforcement Mesh

All floors are reinforced with one layer of A142 mesh laid with lower bars bearing on the ribs of the steel decking. The mesh was tested to BS 4483 by Allied Reinforcements, the average results of these tests are displayed in Table 14.


##### 4.3 Concrete

The concrete is a grade 35 light-weight mix tested to BS 1881 by Contest Melbourne Weeks Limited. The average 7 day and 28 day crushing strength per floor is as shown in Table 15. The 7 day results for floor 1 are considerably higher than the other floors and should be treated with a degree of scepticism.

## **Drawings**


The following drawings have been reproduced at A3 scale and included in this report:

Drawing No.	Drawing Title	Issued by
5992/01	Ground floor steel layout	Peter Brett Associates
5992/02	First floor steel layout	Peter Brett Associates
5992/03	Second floor steel layout	Peter Brett Associates
5992/04	Third to Seventh floor steel layout	Peter Brett Associates
5992/05	Typical Steel Details	Peter Brett Associates
5992/06	Elevation on Gridline A	Peter Brett Associates
5992/07	Roof Steel Layout	Peter Brett Associates
5992/08	First floor steel layout Connection Forces	Peter Brett Associates
5992/09	Second floor steel layout Connection Forces	Peter Brett Associates
5992/10	Third to Seventh floor steel layout Connection Forces	Peter Brett Associates
5992/11	Roof Steel Layout Connection Details	Peter Brett Associates
92066/1	Foundation Plan	Caunton Engineering Ltd
92066/3	Plan on 1st floor steel	Caunton Engineering Ltd
92066/4	Plan on 2nd floor steel	Caunton Engineering Ltd
92066/5	Plan on 3rd floor steel	Caunton Engineering Ltd
92066/6	Plan on 4th floor steel	Caunton Engineering Ltd
92066/7	Elevation on grid lines A & F and sections thru' grid lines C & D ground to 4th floor	Caunton Engineering Ltd
92066/8	Section thru' grid line 2/3 ground to 4th floor	Caunton Engineering Ltd
92066/10	Plan on 5th floor steel	Caunton Engineering Ltd
92066/11	Plan on 6th floor steel	Caunton Engineering Ltd
92066/12	Plan on 7th floor steel	Caunton Engineering Ltd
92066/13	Plan on 8th floor steel	Caunton Engineering Ltd
92066/14	Elevation on grid lines A & F and sections thru' grid lines C & D 5th-8th floor	Caunton Engineering Ltd
92066/15	Section thru' grid line 2/3 5th-8th floor	Caunton Engineering Ltd
Q/6710/01	Typical sections showing Dado wall head restraint details	Convoy Installations Ltd.
Q/6710/02	Typical section showing Dado wall head restraint details	Convoy Installations Ltd.
R1112/01	First floor level Decking Layout	Composite Profiles
R1112/02	Second floor level Decking Layout	Composite Profiles
R1112/03	Third to Seventh floor levels Decking Layout	Composite Profiles
R1112/04	Roof level Decking Layout	Composite Profiles
TE/9202/001	End Elevations & Blockwork Restraint Details	Taywood Engineering Ltd.
TE/9202/002	Front Elevation	Taywood Engineering Ltd.
TE/9202/003	Rear Elevation	Taywood Engineering Ltd.



REFERENCE	DESIGNATION	REMARKS
CO1.BP01 & CO1.BP01A CO1.BP04 CO1.BP08	305x305x198UC 305x305x137UC 254x254x89UC	FOUND. - 2nd ('A' DENOTES 8 BOLT 2nd - 5th HD DETAIL) 5th - ROOF
CO2.BP01 CO2.BP01A CO2.BP01B	305x305x137UC 254x254x89UC	FOUND. - 4th 4th - ROOF
CO2.BP02 CO2.BP08	305x305x137UC 254x254x89UC	FOUND. - 4th 4th - ROOF
CO2.BP04	305x305x137UC 254x254x89UC	FOUND. - 4th 4th - ROOF
CO4.BP02	305x305x198UC	FOUND. - 2nd
CO8.BP03	254x254x89UC	FOUND - ROOF (SPLICED AT FOURTH FLOOR)
CO7.BP06	305x305x137UC 254x254x89UC	2nd - 4th (FOR LOCATION SEE DRG No 5892/03) 4th - ROOF
CO8.BP02	305x305x198UC 254x254x89UC	FOUND - 4th 4th - ROOF

ALL COLUMNS TO BE GRADE 90  
ALL PERIMETER COLUMNS WHEN SPLICED TO BE FLUSH EXTERNALLY



C COLUMNS ABOVE  
F FLOOR LEVEL  
D.G. CO.

REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5992/08	FIRST FLOOR STEEL LAYOUT CONNECTION FORCES
09	SECOND FLOOR STEEL LAYOUT CONNECTION FORCES
10	THIRD - SEVENTH FLOOR STEEL LAYOUT CONNECTION FORCES
11	ROOF STEEL LAYOUT CONNECTION DETAILS

KEY

- ALL BEAMS NOT NOTED ARE 254x146x31UB.
- '\*' APPLIES TO 306x186x40UB RIBS 3000mm LONG WHICH REQUIRE 36mm PRECAMBER.

3. = VOID.

4. = ATRIUM MAJORWAY BY OTHERS.

5. = VERTICAL CROSS BRACED BAYS  
FOUNDATION TO FOURTH FLOOR = 250x18 FLATS (50)  
FOURTH TO ROOF = 200x10 FLATS (50). BRACING TO BE COINCIDENT WITH AXES OF COLUMN.

GENERAL NOTES CONT

- PERIMETER BEAMS ON GRIDS 1 & 4 TO HAVE 4 No HOLES M12 BOLTS FOR ANCON PARAPET POSTS AT 2.25m C/C OR SIMILAR APPROVED (180x70x500 HIGH).
- '\*' DENOTES MEMBER DESIGNED AS KEY ELEMENT TO BS 5950 PART 1. (GROUND TO SECOND FLOOR).

REVISIONS. (CONT'D)

F CO4 ORIENTATION AMENDED. 14/12/92 Jlc

NOTES REVISID.

FOR CONSTRUCTION

GENERAL NOTES.

- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEERS AND STRUCTURAL ENGINEERS DRAWINGS AND SPECIFICATIONS.
  - ALL DIMENSIONS ARE IN MILLIMETRES.
  - DIMENSIONS SHOULD NOT BE SCALED FROM THIS DRAWING.
  - ALL LEVELS ARE IN METRES AND UNLESS OTHERWISE NOTED ARE STRUCTURAL LEVELS.
- STEELWORK:-
- ALL STEEL TO BE BLAST CLEANED. NO PAINTING REQUIRED.
  - ALL STEELWORK TO BE GRADE 43B TO BS4000, TUBES 50C, UNLESS NOTED OTHERWISE.
  - THE STEELWORK CONTRACTOR SHALL BE RESPONSIBLE FOR STABILITY OF THE STRUCTURE DURING ALL STAGES OF ERECTION.
  - ALL BOLTS TO BE M20 (GRADE 8.8) UNLESS NOTED OTHERWISE
  - FRAME TO BE BRACED SIMPLE DESIGN. (BRACING AROUND CENTRAL CORE AND ESCAPE STAIRS)
  - P.B.A. TO COMPLETE OVERALL FRAMING PLAN, REACTIONS ETC. FABRICATOR TO PROVIDE THE CONNECTION CALCULATIONS TO PBA ACCEPTANCE USING ONE OF THE 3 "INDUSTRY" STANDARDS PROMOTED BY SCI/BCSA EXCEPT THE SECOND FLOOR TRANSFER STRUCTURE WHICH WILL BE DESIGNED AND DETAILED JOINTLY BY PBA AND THE FABRICATOR.
  - ALL PERIMETER BEAMS HAVE BEEN DESIGNED TO ALLOW FOR UP TO 200 THK SINGLE SKIN BLOCKWORK (DENSITY < 1400KG/M3) ANY ADDITIONAL CLADDING SHOULD NOT EXCEED AN UNFACTURED LOAD OF 10KV/M2 ON ELEVATION. FINAL SOLUTION TO BE CONFIRMED WITH PBA.
  - STEEL DESIGN STANDARD IS BS.5950.
  - FOR BID PURPOSES ADD 7.5% TO ALL COLUMN AND BEAM WEIGHTS TO ALLOW FOR CONNECTIONS, BASEPLATES & HD BOLTS.

DECKING:-

- PNF DECKING TO BE CONTINUOUS OVER A MINIMUM OF 2 SPANS. SHEETS TO BE FIXED TO SUPPORTING STEEL WITH SHOT FIRED FIXINGS. A MINIMUM OF 2 No FIXINGS AT EACH END OF SHEET AT 500 CENTRES AND 1 No FIXING INTERMEDIATE SUPPORTS.
- SEAMS BETWEEN PNF SHEETS TO BE EITHER RIVETED OR SPOT WELDED AT 1/4 SPAN POINTS.
- JOINTS IN DECKING TO BE TAPED TO PREVENT GROUT LOSS.
- PNF C70 DECK (0.9mm) TO BE USED WITH 1 LAYER A142 MESH IN TOP. SEPERATE R.C. FLOOR PLAN TO BE USED FOR CONSTRUCTION.
- 36mm x 19 DIAMETER SHEAR STUDS OF 300N/MM2 MINIMUM YIELD STRESS ARE TO BE WELDED THROUGH THE DECKING TO ALL SUPPORT BEAMS AT 300 C/C U.M.D. WITH THE 'MELSON' WELD THROUGH TECHNIQUE OR SIMILAR APPROVED. STUD WELDS TO BE CARRIED OUT BY APPROVED OPERATOR.
- CONCRETE TO BE GRADE 35 LIGHT WEIGHT AGGREGATE.

4.1 FLOOR LOADINGS:-

DEAD:- SLAB 2.8 KV/M2  
RAISED FLOOR 0.4 KV/M2  
SERVICES 0.25 KV/M2  
CEILING 0.15 KV/M2  
STEEL SELF WEIGHT 0.25 KV/M2  
PARTITIONS 1.0 KV/M2

ROOF LOADINGS:-

DEAD:- SLAB 2.8 KV/M2  
50 SCREED 1.2 KV/M2  
SERVICES 0.25 KV/M2  
CEILING 0.15 KV/M2  
STEEL SELF WEIGHT 0.25 KV/M2  
LIVE:- PLANT 7.5 KV/M2  
SUPER 0.8KV/M2

REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5992/01	GROUND FLOOR LAYOUT
02	FIRST FLOOR STEEL LAYOUT
03	SECOND FLOOR STEEL LAYOUT
04	THIRD - SEVENTH FLOOR STEEL LAYOUT
05	TYPICAL STEEL DETAILS
06	ELEVATION ON GRIDLINE A
07	ROOF STEEL LAYOUT.

ARCHITECT / RENTAR ARCHITECTS.

E BASEPLATE REFERENCES AMENDED TO SUIT 16/11/92 Jlc

Mark	Revision	Date	Drawn
	RELOCATION OF BUILDING. BRACING SIZES REDUCED		
	CO4 ORIENTATION AMENDED.		
D	COLUMN SIZES AMENDED TO SUIT		
	NEW ROOF LOADS. ANCON POST SPACING ADDED.	30/10/92	Jlc
C	ISSUED FOR BID.		
	BASEPLATE TYPE BPO1A INDICATED/NOTES REV	23/09/92	MS
B	REFERENCE CO8 ADDED ON GRIDS C1 & D1	07/09/92	MS
A	ISSUED FOR INFORMATION	13/08/92	MS


MULTI - STOREY STRUCTURAL AND FIRE TEST FACILITY

GROUND FLOOR STEEL LAYOUT




PETER BRETT ASSOCIATES CONSULTING ENGINEERS

Scale 1:100		Drawing No 5992/01 F	
Date 11/08/92	Drawn JLB	Checked Passed	
Westcoote Road, Reading, Berkshire RG3 2DE. TEL 0734 800791 FAX 0734 697799			







REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5.1	FIRST FLOOR STEEL LAYOUT CONNECTION FORCES
09	SECOND FLOOR STEEL LAYOUT CONNECTION FORCES
10	THIRD - SEVENTH FLOOR STEEL LAYOUT CONNECTION FORCES
11	ROOF STEEL LAYOUT CONNECTION DETAILS

KEY

- ALL BEAMS NOT NOTED ARE 254x146x118.
- \* APPLIES TO 306x166x40UB RIBS 9000mm LONG WHICH REQUIRE 35mm PRECAMBER.

3. = VOID.

4. = ATRIUM MAJORWAY BY OTHERS.

5. VERTICAL CROSS-BRACED BAYE FOUNDATION TO FOURTH FLOOR = 250x15 FLATS (50) FOURTH TO ROOF = 200x10 FLATS (50) BRACING TO BE COINCIDENT WITH AXES OF COLUMNS

GENERAL NOTES CONT

6.1 PERIMETER BEAMS ON GRID 1 & 4 TO HAVE 4 NO HOLES #12 BOLTS FOR ANCHOR PARAPET POSTS AT 2.25m C/C OR SIMILAR APPROVED (180x70x500 HIGH).

6.2 \* DENOTES MEMBER DESIGNED AS KEY ELEMENT TO BE 5000 PART1.

REVISIONS. (CONT-01)

REVISION	DATE	BY
F	14/12/92	Jlc

STUD SPACING REDUCED FOR BEAMS AS SHOWN  
COL ORIENTATION GRID C & D / 2.0m OFFSET  
GRID 2 AMENDED. NOTES REVISED.

FOR CONSTRUCTION

GENERAL NOTES.

- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEERS AND STRUCTURAL ENGINEERS DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS ARE IN MILLIMETRES.
- DIMENSIONS SHOULD NOT BE SCALED FROM THIS DRAWING.
- ALL LEVELS ARE IN METRES AND UNLESS OTHERWISE NOTED ARE STRUCTURAL LEVELS.

STEELWORK:-

- ALL STEEL TO BE BLAST CLEANED. NO PAINTING REQUIRED.
- ALL STEELWORK TO BE GRADE A36 TO B500. TUBES 500. UNLESS NOTED OTHERWISE.
- THE STEELWORK CONTRACTOR SHALL BE RESPONSIBLE FOR STABILITY OF THE STRUCTURE DURING ALL STAGES OF ERECTION.
- ALL BOLTS TO BE 400 (GRADE 8.8) UNLESS NOTED OTHERWISE
- FRAME TO BE BRACED SIMPLE DESIGN. (BRACING AROUND CENTRAL CORE AND ESCAPE STAIRS)
- P.B.A. TO COMPLETE OVERALL FRAMING PLAN, REACTIONS ETC. FABRICATOR TO PROVIDE THE CONNECTION CALCULATIONS TO PBA ACCEPTANCE USING ONE OF THE 3 "INDUSTRY" STANDARDS PROMOTED BY SCI/BCSA EXCEPT THE SECOND FLOOR TRANSFER STRUCTURE WHICH WILL BE DESIGNED AND DETAILED JOINTLY BY PBA AND THE FABRICATOR.
- ALL PERIMETER BEAMS HAVE BEEN DESIGNED TO ALLOW FOR UP TO 200 TMS SINGLE SKIN BLOCKWORK (DENSITY < 1400KG/M<sup>3</sup>) ANY ADDITIONAL CLADDING SHOULD NOT EXCEED AN UNFACTURED LOAD OF 10kN/m<sup>2</sup> ON ELEVATION. FINAL SOLUTION TO BE CONFIRMED WITH PBA.
- STEEL DESIGN STANDARD IS BS.5950.
- FOR B10 PURPOSES ADD 7.5% TO ALL COLUMN AND BEAM WEIGHTS TO ALLOW FOR CONNECTIONS, BASEPLATES & HO BOLTS.

DECKING:-

- PAF DECKING TO BE CONTINUOUS OVER A MINIMUM OF 2 SPANS. SHEETS TO BE FIXED TO SUPPORTING STEEL WITH SHOT FIRED FIXINGS. A MINIMUM OF 2 NO FIXINGS AT EACH END OF SHEET AT 500 CENTRES AND 1 NO FIXING INTERMEDIATE SUPPORTS.
- SEAMS BETWEEN PAF SHEETS TO BE EITHER RIVETED OR SPOT WELDED AT 1/4 SPAN POINTS.
- JOINTS IN DECKING TO BE TAPED TO PREVENT GROUT LOSS.
- PAF C70 DECK (0.9mm) TO BE USED WITH 1 LAYER A142 MESH IN TOP. SEPERATE R.C. FLOOR PLAN TO BE USED FOR CONSTRUCTION.
- 35mm x 19 DIAMETER SHEAR STUDS OF 360N/MM<sup>2</sup> MINIMUM YIELD STRESS ARE TO BE WELDED THROUGH THE DECKING TO ALL SUPPORT BEAMS AT 300mm C.C. WITH THE "NELSON" WELD-THROUGH TECHNIQUE OR SIMILAR APPROVED. STUD WELDS TO BE CARRIED OUT BY APPROVED OPERATOR.
- CONCRETE TO BE GRADE 35 LIGHT WEIGHT AGGREGATE.

4.1 FLOOR LOADINGS:-

DEAD:-	ROOF LOADINGS:-
SLAB 2.8 10kN/m <sup>2</sup>	SLAB 2.8 10kN/m <sup>2</sup>
RAISED FLOOR 0.4 10kN/m <sup>2</sup>	50 SCREENED 1.2 10kN/m <sup>2</sup>
SERVICES 0.25 10kN/m <sup>2</sup>	SERVICES 0.25 10kN/m <sup>2</sup>
CEILING 0.15 10kN/m <sup>2</sup>	CEILING 0.15 10kN/m <sup>2</sup>
STEEL SELF WEIGHT 0.25 10kN/m <sup>2</sup>	STEEL SELF WEIGHT 0.25 10kN/m <sup>2</sup>
LIVE:- IMPOSED 2.5 10kN/m <sup>2</sup>	LIVE:- PLANT 7.5 10kN/m <sup>2</sup>
PARTITIONS 1.0 10kN/m <sup>2</sup>	SUPER 0.80kN/m <sup>2</sup>

REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5.1	GROUND FLOOR LAYOUT
02	FIRST FLOOR STEEL LAYOUT
03	SECOND FLOOR STEEL LAYOUT
04	THIRD - SEVENTH FLOOR STEEL LAYOUT
05	TYPICAL STEEL DETAILS
06	ELEVATION ON ORIGINLINE A
07	ROOF STEEL LAYOUT.

ARCHITECT - PENTAR ARCHITECTS

Mark	Revision	Date	Drawn
E	VERTICAL BRACING SIZE AMENDED	17/11/92	Jlc
	COL ORIENTATION GRID C & D REVISED.		
	P.M.F. / STUD SPACING AMENDED.		
D	SHEAR STUD SPACING AMENDED. BM GRID 2/A-B	30/10/92	Jlc
C	ISSUED FOR B10		
	BRACING SECTION/NOTES REVISED	23/05/92	MS
B	356 UB SECTION AND NOTE 2.7 REVISED	07/05/92	MS
A	ISSUED FOR INFORMATION	13/08/92	MS


MULTI - STOREY STRUCTURAL AND FIRE TEST FACILITY

FIRST FLOOR STEEL LAYOUT




PETER BRETT ASSOCIATES  
CONSULTING ENGINEERS

Scale	1:100	Drawing No	5992/02 F
Date	11/08/92	Drawn	MS
Checked		Passed	



EXTENT OF 300x WELDED TO PLATE



REFERENCE DRAWINGS:-

5.1 DRAWING No	TITLE/CONTENT
5592/01	FIRST FLOOR STEEL LAYOUT CONNECTION FORCES
08	SECOND FLOOR STEEL LAYOUT CONNECTION FORCES
10	THIRD - SEVENTH FLOOR STEEL LAYOUT CONNECTION FORCES
11	ROOF STEEL LAYOUT CONNECTION DETAILS

KEY

- ALL BEAMS NOT NOTED ARE 254x146x31UB.
- "N" APPLIES TO 305x165x40UB RIBS 3000mm LONG WHICH REQUIRE 36mm PRECAMBER.
- = VOID.
- = ATRIUM WALKWAY BY OTHERS.
- = VERTICAL CROSS-BRACED BAYS. FOUNDATION TO FOURTH FLOOR = 250x18 FLATS (50) FOURTH TO ROOF = 200x10 FLATS (50) BRACING TO BE COINCIDENT WITH AXIS OF COLUMNS.

GENERAL NOTES CONT

5.1 PERIMETER BEAMS ON GRID 1 & 4 TO HAVE 4 No HOLES M12 BOLTS @ 225 c/c FOR ANCON PARAPET POSTS AT 2.25m C/C SIMILAR APPROVED (160x70x300 HIGH).

5.2 "\*" DENOTES MEMBER DESIGNED AS KEY ELEMENT TO BE 5550 PART1.

REVISIONS. (CONT'D)

REVISIONS	DATE	BY
F	14/12/92	J1c
STUD SPACING REDUCED FOR BEAMS AS SHOWN		
COL ORIENTATION GRID C & D / 2.0m OFFSET		
GRID 2 AMENDED. NOTES REVISED.		

FOR CONSTRUCTION

GENERAL NOTES.

- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEERS AND STRUCTURAL ENGINEERS DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS ARE IN MILLIMETRES.
- DIMENSIONS SHOULD NOT BE SCALED FROM THIS DRAWING.
- ALL LEVELS ARE IN METRES AND UNLESS OTHERWISE NOTED ARE STRUCTURAL LEVELS.

STEELWORK:-

- ALL STEEL TO BE BLAST CLEANED. NO PAINTING REQUIRED.
- ALL STEELWORK TO BE GRADE 408 TO BS4086, TUBES 50C, UNLESS NOTED OTHERWISE.
- THE STEELWORK CONTRACTOR SHALL BE RESPONSIBLE FOR STABILITY OF THE STRUCTURE DURING ALL STAGES OF ERECTION.
- ALL BOLTS TO BE M20 (GRADE 8.8) UNLESS NOTED OTHERWISE
- FRAME TO BE BRACED SIMPLE DESIGN. (BRACING AROUND CENTRAL CORE AND ESCAPE STAIRS)
- P.B.A. TO COMPLETE OVERALL FRAMING PLAN, REACTIONS ETC. FABRICATOR TO PROVIDE THE CONNECTION CALCULATIONS TO PBA ACCEPTANCE USING ONE OF THE 3 "INDUSTRY" STANDARDS PROMOTED BY SCI/BCSA EXCEPT THE SECOND FLOOR TRANSFER STRUCTURE WHICH WILL BE DESIGNED AND DETAILED JOINTLY BY PBA AND THE FABRICATOR.
- ALL PERIMETER BEAMS HAVE BEEN DESIGNED TO ALLOW FOR UP TO 200 THK SINGLE SKIN BLOCKWORK (DENSITY < 1400KG/M3) ANY ADDITIONAL CLADDING SHOULD NOT EXCEED AN UNFACTURED LOAD OF 10KV/M2 ON ELEVATION. FINAL SOLUTION TO BE CONFIRMED WITH PBA.
- STEEL DESIGN STANDARD IS BS.5950.
- FOR B10 PURPOSES ADD 7.5k TO ALL COLUMN AND BEAM WEIGHTS TO ALLOW FOR CONNECTIONS, BASEPLATES & HD BOLTS.

DECKING:-

- PHF DECKING TO BE CONTINUOUS OVER A MINIMUM OF 2 SPANS. SHEETS TO BE FIXED TO SUPPORTING STEEL WITH SPOT FRIED FIXINGS. A MINIMUM OF 2 No FIXINGS AT EACH END OF SHEET AT 500 CENTRES AND 1 No FIXING INTERMEDIATE SUPPORTS.
- SEAMS BETWEEN PHF SHEETS TO BE EITHER RIVETED OR SPOT WELDED AT 1/4 SPAN POINTS.
- JOINTS IN DECKING TO BE TAPED TO PREVENT GROUT LOSS.
- PHF OF70 DECK (0.9mm) TO BE USED WITH 1 LAYER A142 MESH IN TOP. SEPERATE R.C. FLOOR PLAN TO BE USED FOR CONSTRUCTION.
- 56mm x 19 DIAMETER SHEAR STUDS OF 355N/MM2 MINIMUM YIELD STRESS ARE TO BE WELDED THROUGH THE DECKING TO ALL SUPPORT BEAMS AT 300mm c/c U.N.O. WITH THE "NELSON" WELD-THROUGH TECHNIQUE OR SIMILAR APPROVED. STUD WELDS TO BE CARRIED OUT BY APPROVED OPERATOR.
- CONCRETE TO BE GRADE 35 LIGHT WEIGHT AGGREGATE.

4.1 FLOOR LOADINGS:-

DEAD:- SLAB 2.8 KV/M2	RAISED FLOOR 0.4 KV/M2	DEAD:- SLAB 2.8 KV/M2
SERVICES 0.25 KV/M2	CEILING 0.15 KV/M2	50 SOFFIT 1.2 KV/M2
CEILING 0.15 KV/M2	STEEL SELF WEIGHT 0.25 KV/M2	SERVICES 0.25 KV/M2
LIVE:- IMPOSED 2.5 KV/M2	PARTITIONS 1.0 KV/M2	CEILING 0.15 KV/M2
		STEEL SELF WEIGHT 0.25 KV/M2
		PLANT 7.5 KV/M2
		SUPER 0.8KV/M2

REFERENCE DRAWINGS:-

5.1 DRAWING No	TITLE/CONTENT
5592/01	GROUND FLOOR LAYOUT
02	FIRST FLOOR STEEL LAYOUT
03	SECOND FLOOR STEEL LAYOUT
04	THIRD - SEVENTH FLOOR STEEL LAYOUT
05	TYPICAL STEEL DETAILS
06	ELEVATION ON ORIGINLINE 'A'
07	ROOF STEEL LAYOUT.

ARCHITECT - PENTAR ARCHITECTS

Mark	Revision	Date	Drawn
E	VERTICAL BRACING SIZE AMENDED	17/11/92	J1c
	COL ORIENTATION GRID C & D REVISED.		
	P.M.F. / STUD SPACING AMENDED.		
D	SHEAR STUD SPACING AMENDED. BN.GRID 2/A-B.	30/10/92	J1c
C	ISSUED FOR B10		
	BRACING SECTION-NOTES REVISED	23/08/92	MB
B	356 UB SECTION AND NOTE 2.7 REVISED	07/08/92	MB
A	ISSUED FOR INFORMATION	13/08/92	MB


MULTI - STOREY STRUCTURAL AND FIRE TEST FACILITY

SECOND FLOOR STEEL LAYOUT




PETER BRETT ASSOCIATES  
CONSULTING ENGINEERS

Scale: 1:100		Drawing No: 5592/03 F	
Date: 11/08/92	Drawn: MUM	16 WEYFOTE ROAD, READING, BERKSHIRE RG3 2DE. TEL: 0734 500761. FAX: 0734 597499	
Checked:	Passed:		



5 No FLOORS



REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5892/08	FIRST FLOOR STEEL LAYOUT CONNECTION FORCES
09	SECOND FLOOR STEEL LAYOUT CONNECTION FORCES
10	THIRD - SEVENTH FLOOR STEEL LAYOUT CONNECTION FORCES
11	ROOF STEEL LAYOUT CONNECTION DETAILS

KEY

- ALL BEAMS NOT NOTED ARE 254x146x31UB.
- "\*" APPLIES TO 305x165x40UB RIBS 9000mm LONG WHICH REQUIRE 36mm PRECAMBER.
- = VOID.
- = ATRITION ALLOWAY BY OTHERS.

5. VERTICAL CROSS-BRACED STAIR FOUNDATION TO FOURTH FLOOR = 250x16 FLATS (50) FOURTH TO ROOF = 200x10 FLATS (50) BRACING TO BE COINCIDENT WITH AXES OF COLUMN.

GENERAL NOTES CONT

- PERIMETER BEAMS ON GRID 1 & 4 TO HAVE 4 No HOLES M12 BOLTS FOR ANCON PARAPET POSTS AT 2.25m C/C SIMILAR APPROVED (1500x70x300 HIGH).

REVISIONS. (CONT'D)

Rev	Description	Date	By
F	STUD SPACING REDUCED FOR BEAMS AS SHOWN	11/12/92	Jlc

NOTES REVISED.

FOR CONSTRUCTION

GENERAL NOTES.

- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEERS AND STRUCTURAL ENGINEERS DRAWINGS AND SPECIFICATIONS.
  - ALL DIMENSIONS ARE IN MILLIMETRES.
  - DIMENSIONS SHOULD NOT BE SCALED FROM THIS DRAWING.
  - ALL LEVELS ARE IN METRES AND UNLESS OTHERWISE NOTED ARE STRUCTURAL LEVELS.
- STEELWORK:-
- ALL STEEL TO BE BLAST CLEANED. NO PAINTING REQUIRED.
  - ALL STEELWORK TO BE GRADE 40B TO BS4360, TUBES 50C, UNLESS NOTED OTHERWISE.
  - THE STEELWORK CONTRACTOR SHALL BE RESPONSIBLE FOR STABILITY OF THE STRUCTURE DURING ALL STAGES OF ERECTION.
  - ALL BOLTS TO BE M20 (GRADE 8.8) UNLESS NOTED OTHERWISE
  - FRAME TO BE BRACED SIMPLE DESIGN. (BRACING AROUND CENTRAL CORE AND ESCAPE STAIRS)
  - P.B.A. TO COMPLETE OVERALL FRAMING PLAN, REACTIONS ETC. FABRICATOR TO PROVIDE THE CONNECTION CALCULATIONS TO PBA ACCEPTANCE USING ONE OF THE 3 "INDUSTRY" STANDARDS PROMOTED BY SCI/BCSA EXCEPT THE SECOND FLOOR TRANSFER STRUCTURE WHICH WILL BE DESIGNED AND DETAILED JOINTLY BY PBA AND THE FABRICATOR.
  - ALL PERIMETER BEAMS HAVE BEEN DESIGNED TO ALLOW FOR UP TO 200 THK SINGLE SKIN BLOCKWORK (DENSITY < 1400KG/M3) ANY ADDITIONAL CLADDING SHOULD NOT EXCEED AN UNFACTURED LOAD OF 10KV/M2 ON ELEVATION. FINAL SOLUTION TO BE CONFIRMED WITH PBA.
  - STEEL DESIGN STANDARD IS BS. 5950.
  - FOR BID PURPOSES ADD 7.5% TO ALL COLUMN AND BEAM WEIGHTS TO ALLOW FOR CONNECTIONS, BASEPLATES & HO BOLTS.

DECKING:-

- PMF DECKING TO BE CONTINUOUS OVER A MINIMUM OF 2 SPANS. SHEETS TO BE FIXED TO SUPPORTING STEEL WITH SHOT FIRED FIXINGS. A MINIMUM OF 2 No FIXINGS AT EACH END OF SHEET AT 500 CENTRES AND 1 No FIXING INTERMEDIATE SUPPORTS.
- SEAMS BETWEEN PMF SHEETS TO BE EITHER RIVETED OR SPOT WELDED AT 1/4 SPAN POINTS.
- JOINTS IN DECKING TO BE TAPED TO PREVENT GROUT LOSS.
- PMF C70 DECK (0.9mm) TO BE USED WITH 1 LAYER A142 MESH IN TOP. SEPARATE R.C. FLOOR PLAN TO BE USED FOR CONSTRUCTION.
- 35mm x 19 DIAMETER SHEAR STUDS OF 250N/MM2 MINIMUM YIELD STRESS ARE TO BE WELDED THROUGH THE DECKING TO ALL SUPPORT BEAMS AT 300mm U.N.O. WITH THE "WELSON" WELD-THROUGH TECHNIQUE OR SIMILAR APPROVED. STUD WELDS TO BE CARRIED OUT BY APPROVED OPERATOR.
- CONCRETE TO BE GRADE 35 LIGHT WEIGHT AGGREGATE.

FLOOR LOADINGS:-

- DEAD:- SLAB 2.5 KV/M2
- RAISED FLOOR 0.4 KV/M2
- SERVICES 0.25 KV/M2
- CEILING 0.15 KV/M2
- STEEL SELF WEIGHT 0.25 KV/M2
- LIVE:- IMPOSED 2.5 KV/M2
- PARTITIONS 1.0 KV/M2

ROOF LOADINGS:-

- DEAD:- SLAB 2.5 KV/M2
- 50 SCREED 1.2 KV/M2
- SERVICES 0.25 KV/M2
- CEILING 0.15 KV/M2
- STEEL SELF WEIGHT 0.25 KV/M2
- LIVE:- PLANT 7.5 KV/M2
- SUPER 0.8KV/M2

REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5892/01	GROUND FLOOR LAYOUT
02	FIRST FLOOR STEEL LAYOUT
03	SECOND FLOOR STEEL LAYOUT
04	THIRD - SEVENTH FLOOR STEEL LAYOUT
05	TYPICAL STEEL DETAILS
06	ELEVATION ON ORIGLINE A
07	ROOF STEEL LAYOUT.

ARCHITECT - PENTAR ARCHITECTS

Rev	Description	Date	Drawn
E	VERTICAL BRACING SIZE AMENDED.	17/11/92	Jlc
	P.M.F. / STUD SPACING AMENDED.		
D	SHEAR STUD SPACING AMENDED. BM GRID 2/A-B	30/10/92	Jlc
C	ISSUED FOR BID		
	BRACING SECTION/NOTES REVISED	23/08/92	MS
B	366 UB SECTION AND NOTE 2.7 REVISED	07/08/92	MS
A	ISSUED FOR INFORMATION	13/08/92	MS





MULTI - STOREY STRUCTURAL AND FIRE TEST FACILITY

THIRD TO SEVENTH FLOOR STEEL LAYOUT



PETER BRETT ASSOCIATES CONSULTING ENGINEERS

Scale	1:100	Drawing No	5892/04 F
Date	11/08/92	Drawn	MW
Checked	Passed		




BASE PLATE DETAIL TYPE BPO1 & BPO1A & BPO1B

BASE PLATE DETAIL TYPE BPO2 & BPO3

T.O.F. = TOP OF FOUNDATION

BASE PLATE SIZES FOR TYPES BPO2 & BPO3				
TYPE	A	B	C	D
BPO2	750	350	150	80
BPO3	550	315	115	40
BPO8	900	375	175	70


NOTE:- ALL BASE PLATES TO BE GRADE A3 STEEL




TYPICAL COMPOSITE DETAILS

SE

A. GROUT HOLE.



PLAN




ELEVATION

BASE PLATE DETAIL TYPE BPO4

OF BASEPLT  
LIFTED UP BY  
R NG  
M: UT WITH  
OD MIXTURE  
L  
(AR & APPROVED.)  
ANCE WITH THE  
TIONS.  
R R" H.D. BOLTS  
N DRILLED HOLES  
NG SLAB (T26 @ 150c/c)  
KS 8" RESIN  
OUT BY FOSROC LTD.  
AR & APPROVED) IN FULL  
E WITH MANUFACTURERS  
T)

OG - BPO6



TYPICAL CORNER DETAIL  
SHOWING SETTING OUT

BRACED COLUMN BASEPLATES

(REFERENCE IS MADE TO SKETCH No 1 92086/SK - SK7 SHOWING EXISTING LOCATION OF BOLTS RELATIVE TO PROPOSED HOLES IN BASEPLATE)


1. WHERE AN OVERSIZED HOLE EXISTS THROUGH BASEPLATE THEN ALL VOIDS BETWEEN THE THREAD AND THE EDGE OF THE HOLE ARE TO BE FILLED WITH GROUT AND INSPECTED BY THE ENGINEER PRIOR TO THE WELDING OF ANY PLATES.
2. FOR 50/80mm DIA. OVERSIZED HOLE. - TACK WELD 120x120x15 THK. PLATE.

NOTE

1. DIAMOND DRILLING MAY BE USED IF EXISTING RAFT REINFORCEMENT CLASHES WITH HD BOLT LOCATIONS, BUT FINAL DRILLED HOLES MUST BE ROUGHENED PRIOR TO RESIN GROUTING.
2. ALL BASE PLATES TO BE CONCRETE CASED BY FABRICATOR WITH 75mm COVER.
3. COLUMN TO BASEPLATE CONNECTION TO BE 8mm FILLET WELD (FULL PROFILE) UNLESS NOTED OTHERWISE.
4. REFER TO SKETCH No 1 SK1 & SK2 FOR ANCHOR FIXING / SBFD ANCHOR FIXING DETAILS.

FOR GENERAL NOTES AND SECTION LOCATIONS REFER TO FLOOR LAYOUTS DRG Nos 5922/01-04

CT:



SECTION 4 - 4 SECOND FLOOR ONLY  
TRANSFER BEAM - TYPICAL SECTION

DETAIL AT CONNECTION OF  
TRANSFER BEAM TO COLUMN

ARCHITECT - PENTAR ARCHITECTS.

Mark	Revision	Date	Drawn
E	BASE PLT TYPE BPO18 & BPO6 ADDED	18/11/92	jlc
	TAPERED RODS AMENDED.		
D	BPO3 BASEPLATE THICKNESS AMENDED	27/10/92	jlc
	WELD THICKNESS ADDED.		
C	PLATE ADDED TO SECTION 4 - 4	23/05/92	MS
B	ISSUED FOR BID.		
	HD BOLT DETAILS REVISED	23/05/92	MS
A	ISSUED FOR INFORMATION	13/08/92	MS
Mark	Revision	Date	Drawn

MULTI - STOREY STRUCTURAL  
AND FIRE TEST FACILITY

TYPICAL STEEL DETAILS




PETER BRETT  
ASSOCIATES  
CONSULTING ENGINEERS

16 WESTCOTE ROAD, READING, BERKSHIRE RG32DE, TEL 0734 500761, FAX 0734 597499

Scale	1:10	Drawing No	5992/05 F
Date	11/08/92	Drawn	MS
Checked	Passed		


FOR CONSTRUCTION



S.S.L. = STRUCTURAL SLAB LEVEL

ELEVATION ON GRIDLINE A  
 ELEVATION ON GRIDLINE F SIMILAR BUT HANDED





**SPLICE FORCES (TENSILE)**

BRACED COLUMN SPLICE @ 4th / 5th	T = 620 kN ULT.
BRACED COLUMN SPLICE @ 2nd	T = 1320 kN
NON BRACED EXTERNAL COL. SPLICE	T = 315 kN
NON BRACED INTERNAL COL. SPLICE	T = 430 kN
COLUMN 007 BASEPLATE	T = 860 kN

NOTE:  
REFER TO SKETCH No # SK1 & SK2 FOR ANCON FIXING / SBFD ANCHOR FIXING DETAILS.

FOR GENERAL NOTES REFER TO FLOOR LAYOUTS DRG No# 5392/01-04

ELEVATION ON GRIDLINE C

NOTE  
ALL FORCES ARE ULTIMATE LOADS IN kN

ARCHITECT - PENTAR ARCHITECTS.

Mark	Revision	Date	Drawn
E	ANCON SBFD SPACINGS AMENDED.	15/12/92	Jlc
D	ANCON POSTS TO ATRIUM OMITTED.	16/11/92	Jlc
	SPLICE AT 5th FLOOR LOCATED.		
C	WIND POST ADDED WITHIN ATRIUM AREA.	30/10/92	Jlc
B	ISSUED FOR BID		
	GRID NUMBERS ADDED	23/09/92	MS
A	ISSUED FOR INFORMATION	13/08/92	MS

MULTI - STOREY STRUCTURAL AND FIRE TEST FACILITY


ELEVATION ON GRIDLINE A



**PETER BRETT ASSOCIATES**  
CONSULTING ENGINEERS

pba				
16 WHEATCOTE ROAD, READING, BERKSHIRE RG3 2DE TEL 0734 500761 FAX 0734 597999				
Scales	1:100	Drawing No	5392/06 E	
Date	11/08/92	Drawn		MS
Checked		Passed		


FOR CONSTRUCTION



ROOF PLAN

200x15  
INCL. CD

200x15  
INCL. CD



5000 LONG  
BOTTOM FLANGE

REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5992/08	FIRST FLOOR STEEL LAYOUT CONNECTION FORCES
09	SECOND FLOOR STEEL LAYOUT CONNECTION FORCES
10	THIRD - SEVENTH FLOOR STEEL LAYOUT CONNECTION FORCES
11	ROOF STEEL LAYOUT CONNECTION DETAILS

- KEY
- ALL BEAMS NOT NOTED ARE 254x148x31UB.
  - = VOID.
  - = ATRIUM BALCONY BY OTHERS.
  - = VERTICAL CROSS BRACED BAYS  
FOUNDATION TO FOURTH FLOOR = 250x18 PLATS (50)  
FOURTH TO ROOF = 200x10 PLATS (50) BRACING TO BE  
COINCIDENT WITH AXES OF COLUMN.
  - = 2/3mm WEB PLATES
  - WEB STIFFENERS TO BE PROVIDED AT LOCATION IF  
CONTINUOUS BEAMS OVER COLUMN SUPPORTS.
  - FULL DEPTH FIN PLATE / STIFFENER DENOTED X
  - 4 No 18 DIA. HOLES TO BE PROVIDED IN TOP FLANGE  
FOR CRACLE SUPPORTS. (REFER BK 3)

GENERAL NOTES.

- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEERS AND STRUCTURAL ENGINEERS DRAWINGS AND SPECIFICATIONS.
  - ALL DIMENSIONS ARE IN MILLIMETRES.
  - DIMENSIONS SHOULD NOT BE SCALED FROM THIS DRAWING.
  - ALL LEVELS ARE IN METRES AND UNLESS OTHERWISE NOTED ARE STRUCTURAL LEVELS.
- STEELWORK:-
- ALL STEEL TO BE BLAST CLEANED. NO PAINTING REQUIRED.
  - ALL STEELWORK TO BE GRADE 43B TO BS4000, TUBES 50C, UNLESS NOTED OTHERWISE.
  - THE STEELWORK CONTRACTOR SHALL BE RESPONSIBLE FOR STABILITY OF THE STRUCTURE DURING ALL STAGES OF ERECTION.
  - ALL BOLTS TO BE M20 (GRADE 8.8) UNLESS NOTED OTHERWISE
  - FRAME TO BE BRACED SIMPLE DESIGN. (BRACING AROUND CENTRAL CORE AND ESCAPE STAIRS)
  - P.B.A. TO COMPLETE OVERALL FRAMING PLAN, REACTIONS ETC. FABRICATOR TO PROVIDE THE CONNECTION CALCULATIONS TO PBA ACCEPTANCE USING ONE OF THE 3 "INDUSTRY" STANDARDS PROMOTED BY SCI/BSCA EXCEPT THE SECOND FLOOR TRANSFER STRUCTURE WHICH WILL BE DESIGNED AND DETAILED JOINTLY BY PBA AND THE FABRICATOR.
  - ALL PERIMETER BEAMS HAVE BEEN DESIGNED TO ALLOW FOR UP TO 200 THK SINGLE SKIN SLOOOWORK (DENSITY < 1400KG/M3) ANY ADDITIONAL CLADDING SHOULD NOT EXCEED AN UNFACTURED LOAD OF 10KV/M2 ON ELEVATION. FINAL SOLUTION TO BE CONFIRMED WITH PBA.
  - STEEL DESIGN STANDARD IS BS 5950.
  - FOR B10 PURPOSES ADD 7.5X TO ALL COLUMN AND BEAM WEIGHTS TO ALLOW FOR CONNECTIONS, BASEPLATES & HO BOLTS.

DECKING:-

- PMF DECKING TO BE CONTINUOUS OVER A MINIMUM OF 2 SPANS. SHEETS TO BE FIXED TO SUPPORTING STEEL WITH SHOT FIRED FIXINGS. A MINIMUM OF 2 No FIXINGS AT EACH END OF SHEET AT 500 CENTRES AND 1 No FIXING INTERMEDIATE SUPPORTS.
- SEAMS BETWEEN PMF SHEETS TO BE EITHER RIVETED OR SPOT WELDED AT 1/4 SPAN POINTS.
- JOINTS IN DECKING TO BE TAPED TO PREVENT GROUT LOSS.
- PMF OF70 DECK (0.9mm) TO BE USED WITH 1 LAYER A142 MESH IN TOP. SEPERATE R.O.C. FLOOR PLAN TO BE USED FOR CONSTRUCTION.
- 35mm x 19 DIAMETER SHEAR STUDS OF 350N/MM2 MINIMUM YIELD STRESS ARE TO BE WELDED THROUGH THE DECKING TO ALL SUPPORT BEAMS AT 300 C/C U.N.O. WITH THE 'NELSON' WELD THROUGH TECHNIQUE OR SIMILAR APPROVED. STUO WELDS TO BE CARRIED OUT BY APPROVED OPERATOR.
- CONCRETE TO BE GRADE 35 LIGHT WEIGHT AGGREGATE.

FLOOR LOADINGS:-

- DEAD:- SLAB 2.8 KV/M2  
RAISED FLOOR 0.4 KV/M2  
SERVICES 0.25 KV/M2  
CEILING 0.15 KV/M2  
STEEL SELF WEIGHT 0.25 KV/M2  
LIVE:- IMPOSED 2.5 KV/M2  
PARTITIONS 1.0 KV/M2

ROOF LOADINGS:-

- DEAD:- SLAB 2.8 KV/M2  
50 SCREED 1.2 KV/M2  
SERVICES 0.25 KV/M2  
CEILING 0.15 KV/M2  
STEEL SELF WEIGHT 0.25 KV/M2  
LIVE:- PLANT 7.5 KV/M2  
SUPER 0.6KV/M2

REFERENCE DRAWINGS:-

DRAWING No	TITLE/CONTENT
5992/01	GROUND FLOOR LAYOUT
02	FIRST FLOOR STEEL LAYOUT
03	SECOND FLOOR STEEL LAYOUT
04	THIRD - SEVENTH FLOOR STEEL LAYOUT
05	TYPICAL STEEL DETAILS
06	ELEVATION ON GRIDLINE A
07	ROOF STEEL LAYOUT.

ARCHITECT - PENTAR ARCHITECTS.

Mark	Revision	Date	Drawn
B	RESTRAINTS TO BOTTOM FLANGE OF 810 UB.	16/12/92	Jlc
	ADDED. NOTE 7 ADDED.		
A	STUO SPACING AMENDED. BEAMS GRID C & D BETWEEN GRIDS 1 & 2 AND 3 & 4	19/11/92	Jlc
	WEB PLATES ADDED.		

MULTI - STOREY STRUCTURAL AND FIRE TEST FACILITY  
ROOF STEEL LAYOUT




PETER BRETT ASSOCIATES  
CONSULTING ENGINEERS

14 WESTCOTE ROAD, READING, BERKSHIRE RG3 2DE. TEL 0734 500761. FAX 0734 597496


Scale	1:100	Drawing No	5992/07 B
Date	11/08/92	Drawn	MLW
Checked	Passed		

FOR CONSTRUCTION




- ALL BEAM REACTIONS ARE ULTIMATE LOADS IN kN.
- ALL EDGE BEAM CONNECTIONS TO BE DESIGNED FOR A
- ALL INTERNAL TIE BEAM CONNECTIONS TO BE DESIGNED FOR A
- NOTE: THESE FORCES NEED NOT BE CONSIDERED AS






ALL BEAM REACTIONS ARE ULTIMATE LOADS IN kN.

- ALL EDGE BEAM CONNECTIONS TO BE DESIGNED FOR A TIE FORCE
- ALL INTERNAL TIE BEAM CONNECTIONS TO BE DESIGNED FOR A
- NOTE: THESE FORCES NEED NOT BE CONSIDERED AS ADDITIVE



5 No FLOORS

- ALL BEAM REACTIONS ARE ULTIMATE LOADS IN kN.
- ALL EDGE BEAM CONNECTIONS TO BE DESIGNED FOR A TIE FORCE OF
- ALL INTERNAL TIE BEAM CONNECTIONS TO BE DESIGNED FOR A TENS
- NOTE: THESE FORCES NEED NOT BE CONSIDERED AS ADDITIVE TO




ROOF PLAN

- ALL BEAM REACTIONS ARE ULTIMATE LOADS IN kN.
- ALL EDGE BEAM CONNECTIONS TO BE DESIGNED FOR A TIE FORCE OF
- ALL INTERNAL TIE BEAM CONNECTIONS TO BE DESIGNED FOR A TIE
- NOTE: THESE FORCES NEED NOT BE CONSIDERED AS ADDITIVE TO



GENERAL NOTES.

- 1.1 THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEERS AND STRUCTURAL ENGINEERS DRAWINGS AND SPECIFICATIONS.
- 1.2 ALL DIMENSIONS ARE IN MILLIMETRES.
- 1.3 DIMENSIONS SHOULD NOT BE SCALED FROM THIS DRAWING.
- 1.4 ALL LEVELS ARE IN METRES AND UNLESS OTHERWISE NOTED ARE STRUCTURAL LEVELS.



E.C. 3 kN (ULTIMATE)  
 TENSION FORCE OF 75 kN (ULTIMATE)  
 TO OTHER LOADS

ARCHITECT - PENTAR ARCHITECTS.

Mark	Revision	Date	Drawn
A	REACTION COLUMNS ADDED.	15/12/92	jlc
	TIE FORCES AMENDED.		

MULTI - STOREY STRUCTURAL  
 AND FIRE TEST FACILITY  
 ROOF STEEL LAYOUT  
 CONNECTION DETAILS.




PETER BRETT  
 ASSOCIATES  
 CONSULTING ENGINEERS

pba

11 WHEATCOTE ROAD - READING - BERKSHIRE RG3 2DE - TEL 0734 600761 - FAX 0734 697498

Scale	1:100	Drawing No	5992/11 A
Date	11/08/92	Drawn	MJB
Checked		Posted	

FOR CONSTRUCTION



FOUNDATION PLAN

Specify Steel

# CAUNTON

ENGINEERING LTD.

NATIONAL WORKSHOPS MOORGREEN NOTTINGHAM NG16 3QU

Telephone: 0773 531111

Fax: 0773 532020

CONTRACT:- 2 STORES TEST FACILITY

CLIENT:- B.R.E. CARDINGTON

DRAWN BY:- G. GAFFNEY DATE - 3-12-92 SCALE - 1:100

PAINT NOTE:


HOLE DIA. UNLESS NOTED CHECKED: *[Signature]*

WELD PROCEDURE

FABRICATION TOLERANCES


0-1000mm +OR-1mm  
OVER 1000mm +OR-2mm

REV	DATE	SIG	DESCRIPTION	CHECKED	DATE
A	10/12/92	G.G.	HOLE DIA. & EMBEDMENT DEPTH REVISED	<i>[Signature]</i>	10/12/92
B	15/12/92	G.G.	NOTE ADDED RE. GRouting BASE PLATES	<i>[Signature]</i>	15/12/92





BASE REF. No.	NUMBER OF BASES	No. of HOLES TO DRILL / BASE	HOLE DIA. IN CONC.	STUDING SIZE	EMBEDMENT DEPTH
BPO1	3	No HOLES TO DRILL EXTS. M20 CAST IN SOCKETS	EXISTING CAST-IN SOCKETS	(12 No.) M30 x 275L (B.B)	75 mm.
BPO1A	2	12 No. EXTS. SOCKETS 3 x 4 = 12 TOTAL NEW BOLTS	38 DIA.	12/M30 x 275L (B.B) 12/M30 x 850L (B.B)	75 mm. 650 mm. $\Delta$
BPO1B	ONE	1 x 8 = 8 TOTAL	38 DIA.	8/M30 x 850L (B.B)	650 mm. $\Delta$
BPO2	12	12 x 4 = 48 TOTAL	38 DIA.	48/M24 x 400L REBAR	200 mm.
BPO3	4	4 x 4 = 16 TOTAL	38 DIA.	16/M24 x 400L REBAR	200 mm.
BPO4	7	7 x 8 = 56 TOTAL	38 DIA.	56/M30 x 850L (B.B)	650 mm. $\Delta$
BPO5	N.A.	N.A.	N.A.	N.A.	N.A.
BPO6	3	3 x 4 = 12 TOTAL	38 DIA.	12/M24 x 400L REBAR	200 mm.

NOTE:- RE. ALL BRACED BAS COLUMNS  
BASES REF BPO1, BPO1A, BPO1B & BPO4 TO HAVE  
120 x 120 x 15 THK WASHER PLATES TACK WELDED TO BASE PLATES  
BEFORE WASHER PLATES ARE WELDED IN POSITION THE  
OVERSIZED HOLES ARE TO BE FILLED WITH GROUT (P.B.A.  
ENGINEER TO CHECK PRIOR TO WELDING OF WASHER PLATE.)



DOWN



ENLARGED DETAIL SHOWING  
HOW SECONDARY BEAM  
CONNECTS TO TAB PLATE

PLAN ON 1ST



NOTES:  
 1. ALL ENDS AND FACES MARKED 'E' TO FACE GRID LINE 1


NOTES:  
 → INDICATES DIRECTION FROM WHICH STEEL IS TO BE ERECTED.  
 ALL ENDS AND FACES MARKED 'E' TO FACE GRID LINE 1

REV	DATE	BY	CHKD DATE	DESCRIPTION

NOT SCALE

JOB No: 200803

DATE: 15/11/2008





FLOOR STEEL




CRANTON ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOORE END  
 NOTTINGHAM NG16 5DU

FIG No: 200803  
 JOB No: 200803  
 CLIENT: B.P.F.  
 ADDRESS: 1551

DATE: 15/11/2008  
 DRAWN BY: [Signature]  
 CHECKED BY: [Signature]



ENLARGED DETAIL SHOWING  
HOW SECONDARY BEAM  
CONNECTS TO TAB PLATE




SECTION B-B

PLAN ON C

20-M24 GRAD 12.5 BOLT


NOTE: TYPICAL 4x4  
2 No. STIFFS. Mxd. (C/F)  
SITE WELDED AFTER  
HVE BEEN ERECTED

REV	DATE	BY	CHKD	DATE	DESCRIPTION
A	11/11/82	GG			PLAN BRACING REFORMED




STEEL CONSTRUCTION  
QUALITY ASSURANCE  
SCHEME  
BS 5750 PART 1  
ISO 9000

NOTES:  
→ INDICATES DIRECTION FROM WHICH  
STEEL IS TO BE ERECTED.  
ALL ENDS AND FACES MARKED 'E' TO  
FACE GRID LINE 1



2ND FLOOR STEEL





SECTION A-A




CAUNTUN ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOORGREEN  
 NOTTINGHAM NG16 3DU  
 TELEPHONE (0773) 531111  
 FAX (0773) 532020

DRG No: 92066/4 A		DRAWN BY: J.M.B.
JOB No: 92066	CLIENT: B.R.E.	DATE: 03.12.92
CONTRACT: TEST FACILITY	SITE: CARDINGTON	CHECKED: J.P.
PAINT NOTE: UNPAINTED - BLAST CLEANED		APPROVED:



ENLARGED DETAIL SHOWING  
HOW SECONDARY BEAM  
CONNECTS TO TAB PLATE

PLAN 01N



STEEL CONSTRUCTION  
QUALITY ASSURANCE  
SCHEME  
BS 5750 PART 1  
1SD 3000

NOTES:


- ← INDICATES DIRECTION FROM WHICH STEEL IS TO BE ERECTED
- ALL ENDS AND FACES MARKED 'E' TO FACE GRID LINE 1

REV	DATE	BY	CHKD DATE	DESCRIPTION



NOT SCALE

JOB No: 92066 DRAW No: 001/1





3RD FLOOR STEEL




CAUNTON ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOORGREEN  
 NOTTINGHAM NG16 3QU  
 TELEPHONE (0773) 531111

DRG No:	92066/5	DATE:	03.12.92
JOB No:	92066	CHECKED:	<i>[Signature]</i>
CLIENT:	B.R.E.	APPROVED:	<i>[Signature]</i>
CONTRACT:	TEST FACILITY		
SITE:	CARDINGTON		



ENLARGED DETAIL SHOWING  
HOW SECONDARY BEAM  
CONNECTS TO TAB PLATE


PLAN 01N



STEEL CONSTRUCTION  
QUALITY ASSURANCE  
SCHEME  
BS 5750 PART 1  
150 9000

NOTES:  
← INDICATES DIRECTION FROM WHICH  
STEEL IS TO BE ERECTED  
ALL ENDS AND FACES MARKED 'E' TO  
FACE GRID LINE 1

REV	DATE	BY	CHKD DATE	DESCRIPTION




4TH FLOOR STEEL




CAUNTUN ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOORGREEN  
 NOTTINGHAM NG16 3QU  
 TELEPHONE (0773) 531111

CPG No: 92066/6	DESIGNED BY: ENL
JOB No: 92066	DATE: 03.12.82
CLIENT: B.P.E.	CHECKED: SA
CONTRACT: TEST FACILITY	APPROVED:
SITE: CARDINGTON	




SECTION THRU GRID LINE D




SECTION THRU GRID LINE E




PROJECT NO. 100-100-100-100  
 SHEET NO. 100-100-100-100  
 DATE 10/10/10  
 DRAWN BY 100-100-100-100  
 CHECKED BY 100-100-100-100  
 APPROVED BY 100-100-100-100



ELEVATION ON GRID LINE F




ELEVATION ON GRID LINE A




CONSTRUCTION NOTES  
 ASSURANCE  
 100% GUARANTEE  
 50% ADVANCE PAYMENT  
 50% UPON COMPLETION

REV	DATE	BY	DESCRIPTION

OF THE  
 CONSTRUCTION  
 ASSOCIATION



D LINE 3




D LINE 4


DATE	BY	DESCRIPTION



NO.	REVISION	DATE	BY	DESCRIPTION




SECTION 1-R



1/25 NOT SCALE

JOB No: 92066

DRG No: 92066/10



5TH FLOOR STEEL





CAUNTUN ENGINEERING LTD  
NATIONAL WORKSHOPS  
MOORGREEN  
NOTTINGHAM NG16 3DU  
TELEPHONE (0773) 531111


DRG No: 92066/10  
JOB No: 92066  
CLIENT: B.P.E.  
CONTRACT: TEST FACILITY  
SITE: CARDINGTON

DRAWN BY: J.M.S.  
DATE: 08.12.00  
CHECKED: J.M.S.  
APPROVED:






ENLARGED DETAIL SHOWING  
HOW SECONDARY BEAM  
CONNECTS TO TAB PLATE



STEEL CONSTRUCTION QUALITY ASSURANCE SCHEME BS 5750 PART 1 ISO 9000

NOTES:  
← INDICATES DIRECTION FROM WHICH STEEL IS TO BE ERRECTED.  
ALL ENDS AND FACES MARKED 'E' TO FACE GRID LINE 1

REV	DATE	BY	CHKD DATE	DESCR



6TH FLOOR STEEL



CAUNTUN ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOORGREEN  
 NOTTINGHAM NG16 3DU  
 TEL: (073) 531111

DRG No: 92066/11

JOB No: 92066

CLIENT: B.P.E.

CONTRACT: TEST FACILITY



SITE: CARLINGTON

DRAWN BY: JMB

DATE: 08.12.03


CHECKED: [Signature]

APPROVED: [Signature]



ENLARGED DETAIL SHOWING  
 HOW SECONDARY BEAM  
 CONNECTS TO TAB PLATE

PLG




STEEL CONSTRUCTION  
 QUALITY ASSURANCE  
 SCHEME  
 BS 5750 PART 1  
 ISO 9000

NOTES:

← INDICATES DIRECTION FROM WHICH  
 STEEL IS TO BE ERECTED.  
 ALL ENDS AND FACES MARKED 'E' TO  
 FACE GRID LINE 1

REV	DATE	BY	CHKD DATE	DESCRIP





7th FLOOR STEEL




CAUNTUN ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOORGREEN  
 NOTTINGHAM NG10 30U  
 TELEPHONE (0773) 531111

DRG No: 92066/12	DRAWN BY: JM/SJT
JOB No: 92066	DATE: 08.12.92
CLIENT: B.P.E.	CHECKED: 16/10/92
CONTRACT: TEST FACILITY	APPROVED:
SITE: CAPDONGTON	



ENLARGED DETAIL SHOWING  
 HOW SECONDARY BEAM  
 CONNECTS TO TAB PLATE

PLAN




QUALITY  
**STEEL CONSTRUCTION**  
 QUALITY ASSURANCE  
 SCHEME  
 BS 5750 PART 1  
 ISO 9000

NOTES:  
 ← INDICATES DIRECTION FROM WHICH  
 STEEL IS TO BE ERECTED.  
 ALL FILLS AND FACES MARKED 'E' TO  
 FACE COL. LINE 1


REV	DATE	BY	CHKD DATE	DESRIPTION

NOT SCALE

JOB No: 20056-13





1st FLOOR STEEL




CAUNTUN ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOOPGREEN  
 NOTTINGHAM NG16 3DU  
 TELEPHONE (0773) 531111

JOB No:	20056-13	DESIGNED BY:	DM/ECT
DR No:	20056	DATE:	08.12.92
CLIENT:	B.P.E.	CHECKED:	10/12/92
CONTROL:	TEST FACILITY	APPROVED:	
DATE:	COMPLETION		



ENLARGED DETAIL SHOWING  
HOW SECONDARY BEAM  
CONNECTS TO TAB PLATE


PLAN




STEEL CONSTRUCTION  
QUALITY ASSURANCE  
SCHEME  
BS 5750 PART 1  
150 9000

NOTES:  
← INDICATES DIRECTION FROM WHICH  
STEEL IS TO BE ERRECTED  
ALL ENDS AND FACES MARKED 'E' TO  
FACE C/O LWE 1

REV	DATE	BY	CHKD DATE	DESCRPT



SECTION THRU' GRID LINE D 8TH - 8TH FLOOR



ELEVATION ON GRID LINE A 8TH - 8TH FLOOR







CONSTRUCTION NOTES:  
 1. ALL STEEL TO BE AISC STANDARD ASSURANCE  
 2. ALL WELDS TO BE AISC STANDARD ASSURANCE  
 3. ALL BOLTS TO BE AISC STANDARD ASSURANCE  
 4. ALL BOLTS TO BE AISC STANDARD ASSURANCE  
 5. ALL BOLTS TO BE AISC STANDARD ASSURANCE  
 6. ALL BOLTS TO BE AISC STANDARD ASSURANCE  
 7. ALL BOLTS TO BE AISC STANDARD ASSURANCE  
 8. ALL BOLTS TO BE AISC STANDARD ASSURANCE  
 9. ALL BOLTS TO BE AISC STANDARD ASSURANCE  
 10. ALL BOLTS TO BE AISC STANDARD ASSURANCE

REV	DATE	BY	CHKD	DATE	DESCRIPTION

AS SHOWN ON THE









REV	DATE	BY	CHKD DATE	DESCRIPTION

STILL SHEET




STH - 8TH FLOOR




CALNTON ENGINEERING LTD  
 NATIONAL WORKSHOPS  
 MOORFIELD  
 NOTTINGHAM NG16 5JF  
 TELEPHONE (0773) 931111


APPROVED  
 FOR THE  
 CLIENT  
 BY  
 DATE  
 10/12/90






TYPICAL TO LEVELS 7, 6, AND 5.



TYPICAL TO LEVEL 4.



DATE	REVISION	ISS	DATE	REVISION	NOTES	FINISH UNLESS NOTED



150x75x10 RSA  
( BY OTHERS )

150x75x10 RSA  
( BY OTHERS )

150x75x10 RSA  
( BY OTHERS )

TYPICAL TO LEVEL 4.

150x10 FLAT  
100x10 FLAT ( SPLICE )  
150x75x10 RSA  
( BY OTHERS )

150x10 FLAT  
100x10 FLAT ( SPLICE )  
150x75x10 RSA  
( BY OTHERS )

150x10 FLAT  
100x10 FLAT ( SPLICE )  
150x75x10 RSA  
( BY OTHERS )




TYPICAL TO LEVELS 3, 2, 1, AND GROUND.

100x3 FLAT  
( PACKER )  
180 LONG  
150x10 FLAT  
100x10 FLAT ( SPLICE )  
150x75x10 RSA  
( BY OTHERS )

100x10 FLAT ( SPLICE )  
150x10 FLAT  
150x75x10 RSA  
( BY OTHERS )

100x10 FLAT ( SPLICE )  
150x10 FLAT  
150x75x10 RSA  
( BY OTHERS )

TYPICAL TO LEVELS 3, 2, 1, AND GROUND.




FABRICATION AND INSTALLATION  
OF STRUCTURAL STEELWORK  
AND Light Mechanical Handling  
Equipment, erection and testing of  
Light Overhead Cranes, Runways, etc

ADDRESS  
18 UNION STREET  
LUTON LU1 1AN  
BEDFORDSHIRE  
PHONE (0582) 453534  
FAX (0582) 404118

TITLE  
TYPICAL SECTIONS SHOWING DADO  
WALL HEAD RESTRAINT DETAILS  
BUILDING RESEARCH ESTABLISHMENT  
CARDINGTON, BEDFORDSHIRE.

DRAWN BY A SYMONS  
DATE 11 OCTOBER 1993  
SCALE E5  
DRAWING NUMBER Q/6710/01  
ISSUE





130 COMPOSITE DECKING

SECTION B-B

WELD RSA TO FLAT TO  
AVOID BOLTS CLASHING  
WITH STEELWORK

EXISTING DIA 14 HOLES

BOLT ANGLE TO FLAT  
AFTER CONSTRUCTION  
OF BLOCKWORK WALL  
OF BOLTS @ 100 C/RS

75x50x6 RSA 150 LONG

75x50x6 RSA 150 LONG

140 channel  
section

142 CLEAR  
780  
150x6 FLAT





FABRICATION AND INSTALLATION  
OF STRUCTURAL STEELWORK  
Also Light Mechanical Handling  
Equipment, erection and testing of  
Light Overhead Cranes, Runways, etc

ADDRESS  
18 UNION STREET  
LUTON LU1 3AN  
BEDFORDSHIRE  
PHONE (0582) 453518  
FAX (0582) 404118


TITLE  
TYPICAL SECTION SHOWING DADO  
AND HEAD RESTRAINT DETAILS  
BUILDING RESEARCH ESTABLISHMENT  
CARDINGTON, BEDFORDSHIRE.

DRAWN BY A SYMONS  
DATE 11 OCTOBER 1993  
SCALE 1:5  
DRAWING NUMBER Q/6710/02

ISSUE  
A







- NOTES:**
- All dimensions must be checked on site and not scaled from this drawing.
- GENERAL NOTES**
- This drawing is to be read in conjunction with all other relevant drawings, details and specifications.
  - All decking to be C/P 70 x 0.3 unless otherwise stated.
  - The decking acts as a permanent formwork and tensile reinforcement in the section of the slab only. The design is in accordance with BS 5950 Part 2.
  - The decking will not act as tensile reinforcement to a column or other situation where tensile reinforcement stresses are in the upper surface of the slab. The design and supply of reinforcement in this situation is by others.
  - The overall depth of the slab is 130 mm non-structural concrete. In addition to the self-weight the LIGHTWEIGHT/CONCRETE/STEEL composite. The design loads of the COMPOSITE slab are:
    - LIVE LOAD 2.5 kN/m<sup>2</sup>
    - PARTITIONS 1.0 kN/m<sup>2</sup>
    - FLOOR FINISHES 0.4 kN/m<sup>2</sup>
    - CEILING FINISHES 0.15 kN/m<sup>2</sup>
    - SERVICES 0.25 kN/m<sup>2</sup>
  - The composite slab has been designed only to carry these partitions considered in PWP design calculations.
  - Fire rating for composite slab 1 1/2 hours unless indicated otherwise. It is assumed that the requirements for PWP decking to provide lateral restraint to the beam. (See Table 10.1)
  - Advice on the design of composite slabs and fire resistance may be obtained from PWP Technical Department.
  - All decking to have a suitable bearing of 50mm on structural steelwork and supported by beam on all other materials.
  - No decking to be set down to a single span without consultation with PWP Limited design office.
  - Bearing fixed to steelwork must be secured using flange at 100mm centres at each end and 100mm centres over intermediate supports. The flange are to be either ST11 200/200 or 200/200.
  - Temporary supports (if others) are required where indicated on plan sheet.
  - Concrete must not be allowed to be heaped or dropped from a height onto the deck.
  - For spans exceeding 4.0m with temporary props required, the propping arrangement is to be in place prior to commencement of deck laying.
  - Spreader beams are to be provided in the propping arrangement - see isolated beam area in the propping.
  - Slabs are to be laid per beam measurement as by the main contractor. The maximum size of slab to be 1000mm wide without the removal of part thereof of the slab.
  - Decking to be cut and secured as required with support provided by others.
  - Pre-painted sheets to be able attached at 1.0m centres using self tapping screws.
  - Supplementary steel reinforcement is required in the slab where holes are required by structural steelwork around 100mm transverse to deck span. The design and supply of reinforcement is to be by others.
  - Slab size is dimensioned on plan from the centre line of the beam to the edge of concrete slab.
  - Slab shutter to be secured at 750mm with restraint straps.
  - Steel welding to be carried out in accordance with BS 5135 unless noted otherwise by Composite Floor Construction.
  - Studs shown are 12.5 diameter x 25.5 as height L.A.F.
  - Numbers shown in the 1000mm boxes indicate the number of equally spaced studs.

Date	Revisions
C 7 Jul 93	ADDITIONAL NOTES 4222 (PWP)
B 15 JAN 95	POSITION OF STEELWORK CHANGED
A 22 FEB 92	REVISIONS TO COMPOSITE FLOOR SLAB

© copyright


**Composite Profiles**

15 Moor Road, Broadstone,  
Dorset BH18 8AZ  
Telephone 0202 659237  
Facsimile 0202 659288

Client  
**CAUNTON Engineering Limited**

Job Title  
**CARDINGTON B.R.E.  
MULTI-STORY STRUCTURAL  
AND FIRE TEST FACILITY**

Drawing Title  
**FIRST FLOOR LEVEL  
DECKING LAYOUT**






- ADDITIONAL NOTES:**
- Concrete to be Grade 35 light-weight (Lyttag or similar approved) with a maximum density of 1900 kg/m<sup>3</sup>.
  - All floors to be reinforced with one layer of A142 mesh laid with lower bars bearing on ribs of steel decking.
  - Joints in decking and between decking and structural steelwork to be sealed to prevent great loss from concrete.

Scale 1:75 1:10

Date 1 Dec 92 Drawn by K.S.

Proj No.	R1112/01	Rev.	C
----------	----------	------	---





- NOTES**
- All dimensions must be checked on site and not scaled from this drawing.
- GENERAL NOTES**
- This drawing is to be read in conjunction with all other relevant drawings, details and specifications.
  - All decking to be C70 x 03 unless otherwise stated.
  - The decking acts as a permanent formwork and tensile reinforcement in the bottom of the slab until the concrete is cast.
  - The design is in accordance with BS 5958 Part 4.
  - The decking will not act as tensile reinforcement to a column or other situation where tensile reinforcement stresses are in the upper surface of the slab. The design and supply of reinforcement in this situation is by others.
  - The overall depth of the slab is 120 mm non-combustible COMPOSITE. In addition to the self-weight for **STRUCTURAL/COMPOSITE** concrete.
- The Design Loads of the COMPOSITE slab are:-
- |                  |           |
|------------------|-----------|
| LINE LOAD        | 25 kN/m   |
| PARTITIONS       | 1.0 kN/m  |
| FLOOR FINISHES   | 0.4 kN/m  |
| CEILING FINISHES | 0.15 kN/m |
| SERVICES         | 0.25 kN/m |
- The composite slab has been designed only to carry these partition loads in the design situation.
- Fire rating for composite slab 1 1/2 hours
  - Minimum deflection of slab to be in accordance with BS 5958 Part 4.
  - Advice on the design of composite slab and fire resistance may be obtained from the Technical Department.
  - All decking to have a minimum bearing of 100mm on structural steelwork and concrete and 75mm on all other materials.
  - No decking is to be cut down to a single span without consultation with the Structural Design Office.
  - Decking fixed to structural must be secured using fixings at 100mm centres at each end and 500mm centres over intermediate supports. The fixings are to be either HILTI DSW/DFR nails or STIT fixings etc.
  - Temporary supports (if others) are required where indicated on plan sheet.
  - Concrete must not be allowed to be heaped or dropped from a height onto the deck.
  - For spans exceeding 4.0m with temporary props required, the propping arrangement is to be in place prior to commencement of deck laying.
  - Spreader beams are to be provided in the propping arrangement - no inclined props are to be permitted.
  - Slats cut in the deck for lower clearance are to be main contractor. The maximum size of slit to be 150mm wide without the removal or part thereof of the ribs.
  - Decking to be matched around openings as required with support provided by others.
  - Transverse sheets to be side attached at 100mm centres using self-lapping screws.
  - Supplementary bar reinforcement is required in the slab where holes are drilled by structural steelwork spaced 300mm transversely to each span. The design and supply of reinforcement is to be by others.
  - Slab ribs to be dimensioned on plan from the centre line of the base to the edge of concrete slab.
  - Slab shutter to be secured at 750mm with restraint straps.
  - Stud welding to be carried out in accordance with BS 5958 Part 4.
  - Slab shown are 120mm diameter x 25mm height L.A.P.
  - Reinforcement shown (100mm) bases indicate the number of equally spaced studs.

C	7 Jul 93	'ADDITIONAL NOTES' ADDED (R/rel)
B	15 Jun 92	NOTE 7 AMENDED
A	18 Dec 92	MADE AN ENLIGHTENED CHOICE
	Date	Revisions

© copyright

**Composite Profiles**


15 Moor Road, Broadstone,  
Dorset BH18 8AZ  
Telephone 0202 659237  
Facsimile 0202 659288



Client  
**CAUNTON Engineering Limited**


Job Title  
**CARDINGTON B.R.E. MULTI-STORY STRUCTURAL AND FIRE TEST FACILITY**

Drawing Title  
**SECOND FLOOR LEVEL DECKING LAYOUT**

Scale	1:75
Date	1 Dec
Draw No	R1







- NOTES**
- All dimensions must be checked on site and not scaled from this drawing.
- The decking is to be fixed to the steelwork in accordance with BS 5951 Part 2.
  - All decking to be C70 x 25 unless otherwise stated.
  - The decking acts as a permanent formwork and concrete reinforcement in the slab. The design is in accordance with BS 5951 Part 2.
  - The decking will not act as tensile reinforcement in a cantilever or other situation where tensile reinforcement stresses are in the upper portion of the slab. The design and supply of reinforcement in this situation is to be checked.
  - The overall depth of the slab is 130 mm minimum composite composite. In addition to the self-weight for the composite deck, the design shall also allow for:
    - LIVE LOAD 2.5 kN/m<sup>2</sup>
    - PARTITIONS 1.0 kN/m<sup>2</sup>
    - FLOOR FINISHES 0.4 kN/m<sup>2</sup>
    - CEILING FINISHES 0.15 kN/m<sup>2</sup>
    - SERVICES 0.25 kN/m<sup>2</sup>
  - The composite slab has been designed only to carry those particular loads considered in the design calculations.
  - Fire rating for composite slab: 120 mins.
  - Minimum concrete cover to reinforcement: 20 mm.
  - Advice on the design of composite slabs and fire resistance may be obtained from the Technical Department.
  - All decking to have a minimum bearing of 300 mm on structural steelwork and concrete and 75 mm on all other materials.
  - No decking is to be cut down to a single span without consultation with the design engineer.
  - Decking fixed to steelwork must be secured using fixings at 300 mm centres at each end and 300 mm centres over intermediate supports. The fixings are to be either M12 or 16 mm bolts or 12.9T fixings BS 4449.
  - Temporary supports (struts) are required where indicated on plan sheet.
  - Concrete must not be allowed to be heaped or dropped from a height onto the deck.
  - For spans exceeding 4.0 m temporary props required, the propping arrangement is to be in place prior to commencement of deck laying.
  - Spreader beams are to be provided in the propping arrangement - no isolated props are to be permitted.
  - Slots cut in the deck for bear dimensions are by the main contractor. The bearing size of slots to be 150 mm wide without the removal of part thereof of the ribs.
  - Decking to be pitched around columns as required with support provided by others.
  - Trapezoidal sheets to be side stitched at 150 mm centres using self-lapping screws.
  - Supplementary bar reinforcement is required in the slab where holes are trimmed on structural steelwork exceed 300 mm transverse to deck slab. The design and supply of reinforcement is to be by others.
  - Edge trim is dimensioned on plan from the centre line of the base to the edge of concrete slab.
  - Slope shunter to be secured at 750 mm with restraint straps.
  - Stud welding to be carried out in accordance with BS 1136 Part 1 "Good Practice in Composite Floor Construction".
  - Studs shown are 15 mm diameter x 25 mm height L.S.M.
  - Numbers shown thus 10x300mm base indicate the number of equally spaced studs.

C	7 JUL 91	ADDITIONAL REVISIONS
B	15 JAN 93	SHEET 111 & NOTE 7 AMENDED
A	17 DEC 92	REVISIONS
	Date	Revisions

© copyright


**Composite Profiles**

15 Moor Road, Broadstone,  
Dorset BH18 8AZ  
Telephone 0202 659237  
Facsimile 0202 659288

Client  
**CAUNTON Engineering Limited**

Job Title  
**CARDINGTON B.R.E. MULTI-STOREY STRUCTURAL AND FIRE TEST FACILITY**



Drawing Title  
**THIRD TO SEVENTH FLOOR LEVELS [5<sup>th</sup> THUS] DECKING LAYOUT**




- ADDITIONAL NOTES:**
- Concrete to be Grade 35 light-weight (Lytac or similar approved) with a maximum density of 1900 kg/m<sup>3</sup>
  - All floors to be reinforced with one layer of A142 mesh laid with lower bars bearing on ribs of steel decking
  - Joints in decking and between decking and structural steelwork to be sealed to prevent grout loss from concrete

Scale 1:75 1:10


Date	1 Dec 92	Drawn by	K.S.
Dwg No	R1112/03	Rev	C




1-1




2-2



3-3



4-4



5-5


125.5  
425  
130  
35

REMOVE TO REMOVE CENTRAL RIB IN TROUGH

30 MIN EDGE DIST TO E STUD TYPICAL

STGR STUCC AT EACH SIDE OF J AT BUTT JOINT TYPICAL

FLAS



- NOTES**
- All dimensions must be checked on site and not scaled from this drawing.
- GENERAL NOTES**
- This drawing is to be read in conjunction with all other relevant drawings, details and specifications.
  - All decking to be CP70403 unless otherwise stated.
  - The decking acts as a permanent formwork and tensile reinforcement in the bottom of the slab only. The design is in accordance with BS 5946 Part 4.
  - The decking will not act as tensile reinforcement in a cantilever or other situation where tensile reinforcement stresses are in excess of the design stress. The design and supply of reinforcement in this situation is by others.
  - The overall depth of the slab is 120 mm non-combustible concrete. In addition to the self-weight for LIGHTWEIGHT/STANDARD concrete.
  - The Design Loads of the COMPOSITE slab are:-  
 LIVE LOAD 7.5 kN/m<sup>2</sup>  
 PARTITIONS 1.0 kN/m<sup>2</sup>  
 FLOOR FINISHES 1.2 kN/m<sup>2</sup>  
 CEILING FINISHES 0.15 kN/m<sup>2</sup>  
 SERVICES 0.25 kN/m<sup>2</sup>  
 The composite slab has been designed only to carry these partitions considered in the design calculations.
  - Fire rating for composite slab 1 1/2 hours.
  - Non-combustible concrete to be used for the slab. The design and supply of reinforcement in this situation is by others.
  - Advice on the design of composite slabs and fire resistance may be obtained from PMP Technical Department.
  - All decking to have a minimum bearing of 50mm on structural steelwork and concrete and 75mm on all other materials.
  - No decking is to be cut out to a single span without consultation with PMP design office.
  - Decking fixed to steelwork must be secured using filings at 300mm centres at each end and 500mm centre over intermediate supports. The filings are to be either RILEY EPF/CP nails or SFT filings etc.
  - Temporary supports (if others) are required where indicated on plan sheet.
  - Concrete must not be allowed to be heaped or dropped from a height onto the deck.
  - For spans exceeding 4.5m with temporary props required, the propping arrangement is to be in place prior to commencement of deck laying.
  - Spreader beams are to be provided in the propping arrangement - no isolated props are to be permitted.
  - Sites cut in the deck for beam encasement are to be made contractor. The making site of site to be slope side without the removal of part thereof of the slab.
  - Decking to be notched around columns as required with support provided by others.
  - Transoms sheets to be site stitched at 1.0m centres using self tapping screws.
  - Supplementary bar reinforcement is required in the slab where bars are trimmed by structural steelwork around 100mm transoms to deck span. The design and supply of reinforcement is to be by others.
  - Site cuts in the slab are to be made on the centre line of the beam to the edge of concrete slab.
  - Stop choker to be secured at 75mm with restraint straps.
  - Stud welding to be carried out in accordance with BS 1138 Part 1 "Good Practice in Composite Floor Construction".
  - Studs shown are 15 mm diameter x 55 mm height L.A.S.
  - Numbers shown like 3000mm beams indicate the number of equally spaced studs.

C	7 Jul 93	ADDITIONAL NOTES ADDED BY TEL
B	15 June 93	SECTION 1 & 2 & 7 AMENDED
A	26 Dec 92	MAJOR AMENDMENTS TO DRAWING
	Date	Revisions

© copyright

**Composite Profiles**

15 Moor Road, Broadstone,  
Dorset BH18 8AZ  
Telephone 0202 659237  
Facsimile 0202 659288

Client  
**CAUNTON Engineering Limited**


Job Title  
**CARDINGTON B.R.E. MULTI-STORY STRUCTURAL AND FIRE TEST FACILITY**

Drawing Title  
**ROOF LEVEL DECKING LAYOUT**

Scale 1:75 1:10


Date 1 Dec 92 Drawn by K.S.

Orig No	R 1112/04	Rev	C
---------	-----------	-----	---




**TYPICAL EDGE DETAILS**

- ADDITIONAL NOTES:**
- Concrete to be Grade 35 light-weight (Lyttag or similar approved) with a maximum density of 1900 kg/m<sup>3</sup>
  - All floors to be reinforced with one layer of A142 mesh laid with lower bars bearing on ribs of steel decking
  - Joints in decking and between decking and structural steelwork to be sealed to prevent grout loss from concrete.




ELEVATION ON GRIDLINE A

See note 4



ELEVAT




PLAN DETAILS SHOWING BLOCKWORK



NOTES

1. Figured dimensions only are to be taken from this drawing.



BLOCKWORK HEAD RESTRAINT

2. All blockwork to be "Lignacore" or similar approved either 440 x 215 x 190 x 3 N/mm<sup>2</sup> (max. laid density 1470 kg/m<sup>3</sup>) OR 440 x 215 x 140 x 7 N/mm<sup>2</sup> (max. laid density 2000 kg/m<sup>3</sup>). No special finish required.
3. Mortar to be type (iii) 1:1:5/6 to BS 8000 Pt 3 1989.
4. Where blockwork bears on steelwork, shot fire "Expamet" or similar approved to steelwork to provide a key for the mortar bed.
- Blockwork coursing to be maintained across the facade.
5. All windposts to be supplied and fitted by others.
6. M.S. blockwork ties and restraints acceptable throughout.
7. Blockwork tie fixings to steelwork to have a minimum working load capacity in shear of 0.7 kN.
8. Blockwork to be laid in a continuous straight line between adjacent columns parallel to the line between the outside facades of the columns. The line of the outside face of the walls on G.L.'s 19+ is to be set to the inner most face of the dado rail head restraint (see CA1/3). The top courses or courses on G.L.'s A & F are to be uncut. Cut blocks necessary to form the correct fit to the beam soffit are to be laid immediately below the top course (Ref: CA1).
9. The top courses or courses on G.L.'s A & F are to be uncut. Cut blocks necessary to form the correct fit to the beam soffit are to be laid immediately below the top course (Ref: CA1).

Panels adjacent to 1/F deleted. Notes B & 9 added. Hole for gas pipes added. Plan details & head restraint revised.	2/12/93	G.P.		A
TENDER ISSUE	22/7/93	MJS		
REVISION	DATE	INL	APPD	No
SCALE	1:100 & 1:5	Drawn G.P.	Date JUNE '93	
		Checked MJS	Date 25/7/93	

APPROVED


This drawing is copyright and may not be reproduced or made use of unless expressly agreed by Taywood Engineering Limited

PROJECT  
B.R.E. CARDINGTON - TEST FACILITY

DRAWING TITLE  
END ELEVATIONS & BLOCKWORK RESTRAINT DETAILS

Taywood Engineering Limited  
345 Ruislip Road,  
Southall, Middlesex. UB1 2QX  
Tel. 081-578 2366

*(Handwritten signature)*



Typical panel showing blockwork ties and head restraint setting out 4th floor to roof.


Typical panel showing blockwork ties and head restraint setting out ground to 4th floor.

Leave hole around gas pipes to nearest half block with minm. 25mm clearance all round.

Omit for Access


Cross bracing

... ON GRIDLINE F




... FIXINGS

F



ELEVATION ON GRIDLINE 1



DRAWING No  
TE/9202/002 A

NOTES

1. Figured dimensions only are to be taken from this drawing.
2. For details of blockwork tie fixings refer to drawing No TE/9202/001.
3. For blockwork and mortar types refer to drg. No TE/9202/001.

Panel adjacent to grid 1/F divided	2/12/93	G.P.		A
TENDER ISSUE	23/7/93	AJW		
REVISION	DATE	INL	APPD	No
SCALE	Drawn G.P.		Date JUNE '93	
1:100	Checked AJW		Date 23/7/93	

APPROVED


This drawing is copyright and may not be reproduced or made use of unless expressly agreed by Taywood Engineering Limited

PROJECT  
B.R.E. CARDINGTON - TEST FACILITY

DRAWING TITLE  
FRONT ELEVATION

**Taywood Engineering Limited**  
345 Ruislip Road,  
Southall, Middlesex. UB1 2QX  
Tel. 081-578 2366

DRAWING No  
TE/9202/002 A



SECTION 2-3  
G.L. ①

ELEVATION ON GRIDLINE 4/1 (HANDLED)

G.L. ① ONLY  
(ATRIUM)

LEAVE OPEN ?  
G.L. ① + ④  
yes

e.g. Bolt baseplate  
= concrete for all WP's on 3. floor  
(Provide detail for approval)


ELIMINARY

DRAWING No

TE/9202/003

## NOTES

1. Figured dimensions only are to be taken from this drawing.
2. For details of blockwork the fixings refer to drawing No TE/9202/001.
3. For blockwork and mortar types refer to drg No TE/9202/001.



SKETCH BRE/WP/DWC/4

WINDPOST LOCATIONS

ROOF POST LOCATIONS

PRELIMINARY

REVISION	DATE	INL	APPD	NO
SCALE	Drawn	GP	Date	JUNE '93
1:100	Checked		Date	

APPROVED

This drawing is copyright and may not be reproduced or made use of unless expressly agreed by Taywood Engineering Limited

PROJECT

B.R.E CARDINGTON - TEST FACILITY

DRAWING TITLE

REAR ELEVATION

Taywood Engineering Limited

345 Ruislip Road,  
Southall, Middlesex. UB1 2QX

Tel. 081-578 2366

DRAWING No

TE/9202/003

**Table 1 : Lackenby steelwork testing results**

<b>Bar marking</b>	<b>Cast number</b>	<b>Section</b>	<b>Yield strength (N/mm<sup>2</sup>)</b>	<b>UTS (N/mm<sup>2</sup>)</b>	<b>Elongation (%)</b>
737723	7C27212	305*305*198UC	394	525	27
157412	7C27212	305*305*198UC	391	534	27
157413	7C27212	305*305*198UC	387	535	23
737730	7C14793	305*305*137UC	399	533	27
157420	7C14793	305*305*137UC	390	548	27
737729	7C27067	305*305*137UC	389	512	27
158082	7C27833	610*229*101UB	315	482	27
158083	7C27833	610*229*101UB	313	483	24
157665	7C15290	686*254*170UB	390	526	25

Table 2 : Shelton steelwork testing results (356\*171\*51UB)

	A			B			C			D			E			F		
	YS	UTS	Elg	YS	UTS	Elg	YS	UTS	Elg	YS	UTS	Elg	YS	UTS	Elg	YS	UTS	Elg
	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%
1	402	556	23							390	543	29	-	-	-	-	-	-
	-	-	-	-	-	-	-	-	-	391	542	28	-	-	-	-	-	-
2	418	552	27							387	538	27	-	-	-	-	-	-
3	393	542	28							382	530	27	-	-	-	-	-	-
4	395	541	22							376	530	27	-	-	-	-	-	-
5	392	554	29							374	531	27	-	-	-	-	-	-
6	387	541	24							375	534	28	-	-	-	-	-	-
7	401	555	26							390	541	29	-	-	-	-	-	-
8	391	548	23							395	549	27	-	-	-	-	-	-
9	?	?	?	?	?	?	?	?	?	?	?	?	-	-	-	-	-	-
10	396	547	25										384	532	29	-	-	-
11	396	550	25							389	544	29	-	-	-	-	-	-
12	392	544	25							387	545	29	-	-	-	-	-	-
13	390	540	27							385	535	26	-	-	-	-	-	-
14	389	543	25							383	542	27	-	-	-	-	-	-
15	371	519	25							371	530	27	-	-	-	-	-	-
16	379	529	25							381	536	29	-	-	-	-	-	-
17	390	540	24							379	541	25	387	507	28	-	-	-
18	394	554	25										399	544	28	-	-	-
19	386	531	26										379	514	28	-	-	-
20	399	549	25										381	527	26	379	527	27
21	393	541	25										393	539	25	-	-	-
22	399	556	24										398	545	26	?	?	?
23	382	535	24													384	535	28
24	393	548	25													379	530	29
25	404	551	25													390	547	27
26	399	551	27										395	543	27	-	-	-
27	383	535	24	397	537	29							?	?	?	-	-	-
28	391	548	26										388	538	26	-	-	-
29	396	549	24										413	561	28	-	-	-
30	397	550	25										397	542	28	-	-	-

**Notes:**

There are two results for 1D.

There are no results for bar 9.

There shouldn't be a bar 10E according to John Dowling (JD), but one is marked in the building.

There shouldn't be both 17D and 17E, infact no bars marked 17E appear in the building.

Ditto 22E and 22F.

There is a bar 22F in the building but the results are for 22E.

There should be a bar 27E according to JD but none are marked in the building, 27A and 27B are marked.

There are bars marked 3F and 33F identified in the building, the latter being particularly curious.

Table 3 : Shelton steelwork testing results (254\*254\*89UC)

	A			B			C			D			E		
	YS	UTS	Elg	YS	UTS	Elg	YS	UTS	Elg	YS	UTS	Elg	YS	UTS	Elg
	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%	N/mm <sup>2</sup>		%
1	391	554	31										?	?	?
2	393	558	25										?	?	?
3	?	?	?										?	?	?
4	381	555	26										392	548	27
5	384	543	24										?	?	?
6	384	540	28	378	532	27	-	-	-	-	-	-	-	-	-
	379	538	25	-	-	-	-	-	-	-	-	-	-	-	-
7	385	541	26										390	537	28
8	379	537	27	359	528	29	-	-	-	-	-	-	-	-	-

Notes:  
 1E, 2E, 3A, 3E and 5E are missing  
 There are two values for 6A



Table 4 : Scunthorpe steelwork testing results (average of 3 tests per bar)

Cast number	Bar number	Yield strength (N/mm <sup>2</sup> )	UTS (N/mm <sup>2</sup> )	Elongation (%)
64415	501	312	476	27
64415	506	310	475	26
64415	507	315	475	27
64415	509	318	474	28
64415	511	314	475	27
64415	513	311	472	28
64415	516	316	472	27
64415	518	313	476	28
64415	521	313	472	27
64415	523	316	473	28
64415	525	313	475	28
64415	526	297	472	28
64415	527	309	475	30
64419	530	304	473	28
64419	531	317	476	28
64419	533	309	472	27
64419	535	310	474	28
64419	537	308	472	27
64419	538	309	470	28
64419	539	315	474	25
64419	540	311	475	27
64419	542	304	473	28
64419	544	308	464	26
64419	545	310	470	28
64419	546	309	473	29
64419	547	306	472	29
64419	548	311	474	27
64419	550	299	466	28
64419	552	306	464	27
64419	555	299	472	29
64419	557	301	475	27
64419	559	299	463	27
64419	560	307	473	29
64419	561	312	476	28
64419	562	309	473	27
64419	563	312	471	27
64419	564	299	473	27
64419	565	307	472	28
64419	567	302	469	28
64419	569	298	468	28
64419	571	305	467	28
64419	573	300	470	28
64419	575	310	467	29
64419	577	304	465	26
64419	581	291	469	28
64419	605	311	469	27

**Table 5 : Mill release results for members marked with cast numbers only**

Bar marking	Source	Section	Yield strength (N/mm <sup>2</sup> )	UTS (N/mm <sup>2</sup> )	Elongation (%)
4572	Shelton	356*171*51UB	412	550	21
737721	Lackenby	305*305*198UC	391	534	27
157419	Lackenby	305*305*137UC	389	512	27
63988	Scunthorpe	254*146*31UB	342	499	26
64419	Scunthorpe	305*165*40UB	302	471	28

Table 6 : Average results of nut and bolt testing.

Diameter (mm)	Length (mm)	Tensile Strength (N/mm <sup>2</sup> )	Elongation (%)
		Average	Average
M24	120	851	17.7
M24	80	849	17.5
M20	50	881	15.3
M20	70	888	15.3
M20	80	897	15.6
M20	90	888	15.6
M20	100	877	15.8
M20	110	859	16.0

Table 7 : Column base plate details

Column Ref.	Floor	Square dimension (mm)	Thickness of Base Plate (mm)	Weld leg length (mm)	Number of bolts	Type of bolt	Depth drilled into slab (mm)
A1	G	550	40	6	4	M24 Rebar	200
A2	G	900	70	6	4	M30 (8.8) FT	125 (S)
A2/3	G	750	60	12	8	M30 (8.8) FT	650
A3	G	900	70	12	4	M30 (8.8) FT	650
A4	G	550	40	6	4	M24 Rebar	200
A/B2/3	G	750	60	6	4	M24 Rebar	200
A/B3	G	750	60	12	8	M30 (8.8) FT	650
B1	G	750	60	6	4	M24 Rebar	200
B2	G	900	70	6	4	M30 (8.8) FT	125 (S)
B3	G	900	70	6	4	M30 (8.8) FT	125 (S)
B4	G	750	60	6	4	M24 Rebar	200
C1	G	750	60	6	4	M24 Rebar	200
C2	2	500*650	40	6	8	M24 (8.8)	N/A
C2	G	750	60	6	4	M24 Rebar	200
C2/3	G	750	60	12	8	M30 (8.8) FT	650
C3	G	900	70	12	4	M30 (8.8) FT	650
C4	G	750	60	6	4	M24 Rebar	200
C/D2/3	G	750	60	12	8	M30 (8.8) FT	650
all remaining are mirror images of the above except							
E2	G	900	70	6	4	M24 Rebar	200
E3	G	900	70	6	4	M24 Rebar	200
F2	G	900	70	6	4	M24 Rebar	200
F3	G	900	70	12	8	M30 (8.8) FT	650
Key	-	-	-	-	-	FT=Fully Threaded	S=M30 socket

**Table 8 : Specification of different styles of splice used.**

Splice type Ref. number	Splice type, C&B or W&F	Dimensions of plates (mm)			Number of bolts		
		Cap and Base plates (C & B)	Web cover plate (W & F)	Flange cover plate	Cap and Base plates	Web cover plate	...per flange cover plate
1	C&B	350*370&30Thk	-	-	6	-	-
2	C&B	350*370&35Thk	-	-	4	-	-
3	C&B	350*350&20Thk	-	-	6	-	-
4	C&B	350*350&25Thk	-	-	6	-	-
5	C&B	350*350&30Thk	-	-	4	-	-
6	C&B	280*280&20Thk	-	-	4	-	-
7	W&F	-	180*180&6Thk	130*900&12Thk	-	4	5

**Table 9 : The location and type of splice used on each column.**

Column Ref.	Splice on floor	splice from..	to..	Type of Splice
A1	4th	254*254*89	254*254*89	6
A2	4th	305*305*137	254*254*89	3
A2/3	4th	305*305*137	254*254*89	4
A3	4th	305*305*137	254*254*89	4
A4	4th	254*254*89	254*254*89	6
A/B2/3	4th	305*305*137	254*254*89	3
A/B3	4th	305*305*137	254*254*89	4
B1	4th	305*305*137	254*254*89	5
B2	2nd	305*305*198	305*305*137	1
	5th	305*305*137	254*254*89	3
B3	2nd	305*305*198	305*305*137	1
	5th	305*305*137	254*254*89	3
B4	4th	305*305*137	254*254*89	5
C1	4th	305*305*198	254*254*89	2
C2	4th	305*305*137	254*254*89	3
C2/3	2nd	305*305*198	305*305*137	7
	5th	305*305*137	254*254*89	4
C3	2nd	305*305*198	305*305*137	7
	5th	305*305*137	254*254*89	4
C4	4th	305*305*137	254*254*89	5
C/D2/3	2nd	305*305*198	305*305*137	7
	5th	305*305*137	254*254*89	4

The east end of the building is a mirror image of the west.

**Table 8 : Specification of different styles of splice used.**

Splice type Ref. number	Splice type, C&B or W&F	Dimensions of plates (mm)			Number of bolts		
		Cap and Base plates (C & B)	Web cover plate (W & F)	Flange cover plate	Cap and Base plates	Web cover plate	...per flange cover plate
1	C&B	350*370&30Thk	-	-	6	-	-
2	C&B	350*370&35Thk	-	-	4	-	-
3	C&B	350*350&20Thk	-	-	6	-	-
4	C&B	350*350&25Thk	-	-	6	-	-
5	C&B	350*350&30Thk	-	-	4	-	-
6	C&B	280*280&20Thk	-	-	4	-	-
7	W&F	-	180*180&6Thk	130*900&12Thk	-	4	5

**Table 9 : The location and type of splice used on each column.**

Column Ref.	Splice on floor	splice from..	to..	Type of Splice
A1	4th	254*254*89	254*254*89	6
A2	4th	305*305*137	254*254*89	3
A2/3	4th	305*305*137	254*254*89	4
A3	4th	305*305*137	254*254*89	4
A4	4th	254*254*89	254*254*89	6
A/B2/3	4th	305*305*137	254*254*89	3
A/B3	4th	305*305*137	254*254*89	4
B1	4th	305*305*137	254*254*89	5
B2	2nd	305*305*198	305*305*137	1
	5th	305*305*137	254*254*89	3
B3	2nd	305*305*198	305*305*137	1
	5th	305*305*137	254*254*89	3
B4	4th	305*305*137	254*254*89	5
C1	4th	305*305*198	254*254*89	2
C2	4th	305*305*137	254*254*89	3
C2/3	2nd	305*305*198	305*305*137	7
	5th	305*305*137	254*254*89	4
C3	2nd	305*305*198	305*305*137	7
	5th	305*305*137	254*254*89	4
C4	4th	305*305*137	254*254*89	5
C/D2/3	2nd	305*305*198	305*305*137	7
	5th	305*305*137	254*254*89	4

The east end of the building is a mirror image of the west.

**Table 10 : Standard Column to Beam connections.**

Supporting Column	Supported Member	Thickness of End plate (mm)	Size of Fillet weld	Number of Bolts	Exceptions
305*305*198UC	610*229*101UB	10	6	14	None
	356*171*51UB	8	6	8	C3 (E), D3 (W) Floors 1-2
	305*165*40UB	8	6	8	None
	305*305*198UC	12	8	8	None
305*305*137UC	610*229*101UB	10	6	14	None
	356*171*51UB	8	6	8	C3 (E), D3 (W) Floors 2-5
	305*165*40UB	8	6	8	None
	254*146*31UB	8	6	6	None
254*254*89UC	610*229*101UB	10	6	14	None
	356*171*51UB	8	6	8	C3(E), D3(W), Floors 5-7, C1(N), C4(S), D1(N), D4(S) Roof
	305*165*40UB	8	6	8	None
	254*146*31UB	8	6	6	None
<b>Exceptions:</b>					<b>location</b>
305*305*198UC	356*171*51UB	20	8	8	C3 (E), D3 (W) Floors 1-2
305*305*137UC	356*171*51UB	20	8	8	C3 (E), D3 (W) Floors 2-5
254*254*89UC	356*171*51UB	20	8	8	C3(E), D3(W), Floors 5-7
254*254*89UC	356*171*51UB	8	6	10	C1(N), C4(S), D1(N), D4(S) Roof

**Table 11 : Standard Beam to Beam connections.**

Supported Member	Supporting Member	Thickness of Fin Plate (mm)	Size of Fillet weld (mm)	Number of bolts
254*146*31UB	254*146*31UB	?	?	?
254*146*31UB	305*165*40UB	10	8	3
254*146*31UB	356*171*51UB	?	?	?
305*165*40UB	254*146*31UB	10	8	3
305*165*40UB	305*165*40UB	10	8	4
305*165*40UB	356*171*51UB	10	8	4
305*165*40UB	610*229*101UB	10	8	4
356*171*51UB	356*171*51UB	10	8	4

Table 12 : Second floor transfer structure beam to beam connection details

Supported Member	Type of plate	Thickness of Plate (mm)	Size of Fillet weld (mm)	Number of bolts
305*305*198UC	End	12	8	8
305*165*40UB	End	8	6	6
356*171*51UB	Fin	10	8	4

Table 13 : Primary beam connection to continuous beams at roof level

Supported Member	Supporting Member	Thickness of Toe Plate (mm)	Thickness of Fin/End Plate (mm)	Size of Fillet weld (mm)	Number of bolts
356*171*51UB	610*229*101UB	10	10 (F)	8	4
305*165*40UB	610*229*101UB	10	10 (F)	8	4
356*171*51UB	356*171*51UB	20	20 (E)	8	8
305*165*40UB	356*171*51UB	10	10 (F)	8	4

Table 14 : Average results of reinforcement mesh testing.


0.2% Proof Stress (N/mm <sup>2</sup> )	Maximum Stress (N/mm <sup>2</sup> )	Elongation (%)	Weld strength (kN)
629	732	14.3	14.2


Table 15 : Average 7 and 28 day cube crushing strength of concrete from the floors.

Floor	Crushing strength (N/mm <sup>2</sup> )	
	7 day	28 day
1	41.3	48.0
2	25.5	45.8
3	26.6	45.5
4	24.3	46.7
5	26.5	50.7
6	28.3	48.2
7	26.2	48.7
8	25.2	43.7
all floors	28.0	47.1
all floors excluding floor 1	26.1	47.0

## Figures








FLOOR 1

Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 1

Key:

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member





FLOOR 2


Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 2

Key :

- Test result available
- ◊ Value interpolated from other results
- Value available from mill release certificates
- ◻ ? No marking identified on member









FLOOR 3

Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 3

Key:

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member










FLOOR 4


Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 4

Key:

-  Test result available
-  Value interpolated from other results
-  Value available from mill release certificates
-  No marking identified on member









FLOOR 5

Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 5

Key :

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member







FLOOR 6

Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 6

Key:

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member







FLOOR 7

Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 7

Key:

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member






ROOF PLAN

Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 8

- Key:
- Test result available
  - Value interpolated from other results
  - Value available from mill release certificates
  - No marking identified on member







Cardington LBTF Steelwork Testing  
 Member Identification Plan  
 Figure 9

Key :

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- No marking identified on member

ELEVATION ON GRIDLINE A




Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 10

Key:

- Test result available
- Value interpolated from other results
- Value available from mill release certificate
- ? No marking identified on member

ELEVATION ON GRIDLINE A/B




Cardington LBTF Steelwork Testing  
 Member Identification Plan  
 Figure 11

Key:

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member

ELEVATION ON GRIDLINE B





Cardington LBTF Steelwork Testing Member Identification Plan  
 Figure 12

Key:

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member


ELEVATION ON GRIDLINE C



Cardington LBTf Steelwork Testing  
 Member Identification Plan  
 Figure 13

- Key :
- Test result available
  - Value interpolated from other results
  - Value available from mill release certificates
  - ? No marking identified on member

ELEVATION ON GRIDLINE C/D




Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 14

Key:

ELEVATION ON GRIDLINE D



- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member



Cardington LBTF Steelwork Testing  
 Member Identification Plan  
 Figure 15

Key:  
 Test result available  
 Value interpolated from other results  
 Value available from mill release certificates  
 ? No marking identified on member

ELEVATION ON GRIDLINE E



1


Cardington LBTF Steelwork Testing  
Member Identification Plan  
Figure 16

Key :

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member

ELEVATION ON GRIDLINE E/F





Cardington LBT Steelwork Testing  
 Member Identification Plan  
 Figure 17


Key :

- Test result available
- Value interpolated from other results
- Value available from mill release certificates
- ? No marking identified on member

ELEVATION ON GRIDLINE E


Sketches

NB THIS IS A BRE REF. NO.



Wind post fixing details gridlines A and B

NB. THIS IS A BRE REF. NO.



Windpost fixing details - grid lines 1 and 4

## Appendices

# Appendix A : Cardington LBTF Drawing List

DR

Drawing No.	Drawing Title	Issue
5992/01	Ground floor steel layout	Peter Brett Assoc
5992/02	First floor steel layout	Peter Brett Assoc
5992/03	Second floor steel layout	Peter Brett Assoc
5992/04	Third to Seventh floor steel layout	Peter Brett Assoc
5992/05	Typical Steel Details	Peter Brett Assoc
5992/06	Elevation on Gridline A	Peter Brett Assoc
5992/07	Roof Steel Layout	Peter Brett Assoc
5992/08	First floor steel layout Connection Forces	Peter Brett Assoc
5992/09	Second floor steel layout Connection Forces	Peter Brett Assoc
5992/10	Third to Seventh floor steel layout Connection Forces	Peter Brett Assoc
5992/11	Roof Steel Layout Connection Details	Peter Brett Assoc
6101/01	Contractors areas & access routes	Peter Brett Assoc
6101/02	Existing services layout	Peter Brett Assoc
6101/03	Surface water drainage layout	Peter Brett Assoc
6101/04	G.A. & Details of raft foundation	Peter Brett Assoc
92066/1	Foundation Plan	Caunton Enginee
92066/2	Isometric view of steel frame	Caunton Enginee
92066/3	Plan on 1st floor steel	Caunton Enginee
92066/4	Plan on 2nd floor steel	Caunton Enginee
92066/5	Plan on 3rd floor steel	Caunton Enginee
92066/6	Plan on 4th floor steel	Caunton Enginee
92066/7	Elevation on grid lines A & F and sections thru' grid lines C & D	Caunton Enginee
92066/8	Section thru' grid lines 2/3	Caunton Enginee
92066/10	Plan on 5th floor steel	Caunton Enginee
92066/11	Plan on 6th floor steel	Caunton Enginee
92066/12	Plan on 7th floor steel	Caunton Enginee
92066/13	Plan on 8th floor steel	Caunton Enginee
92066/15	Section thru' grid lines 2/3 5th-8th floor	Caunton Enginee
Q/6710/01	Typical sections showing Dado wall head restraint details	Convoy Installatic
Q/6710/02	Typical section showing Dado wall head restraint details	Convoy Installatic
R1112/01	First floor level Decking Layout	Composite Profile
R1112/02	Second floor level Decking Layout	Composite Profile
R1112/03	Third to Seventh floor levels Decking Layout	Composite Profile
R1112/04	Roof level Decking Layout	Composite Profile
TE/9202/001	End Elevations & Blockwork Restraint Details	Taywood Enginee
TE/9202/002	Front Elevation	Taywood Enginee
TE/9202/003	Rear Elevation	Taywood Enginee
<b>Annotated drawings and others</b>		
	Member identification plans for the steelwork testing	Plans prepared b
	Crack survey of composite concrete floors	Survey conducte
	Negatives of drawings R1112/01 to R1112/04	



**Appendix B : Details of rolling mill test procedure**

To be supplied by John Dowling of British Steel (0642 474111).