

CM01 – Concrete and Masonry Structures 1

HW5 – Drawings of reinforcement



Author: Jakub Holan


Last update: 21.10.2022 14:43

Task 1

Task 1 – Frame structure

In Task 1, frame structure will be designed.








Task 1 – Assignment

Scheme of the stucture:

Plan:



Individual parameters (parameters in **bold** you can find on teacher's website):

Geometry: R, a [m] – horizontal dimensions, h [m] – floor height, n – number of floors

Materials: Concrete - concrete class

Steel B 500 B ($f_{vk} = 500 \text{ MPa}$)

Loads: Other permanent load of typical floor $(g-g_0)_{floor,k}$ [kN/m²]

Other permanent load of the roof $(g-g_0)_{roof,k}$ [kN/m²]

Live load of typical floor $q_{floor,k}$ [kN/m²] Live load of the roof $q_{\text{roof,k}} = 0.75 \text{ kN/m}^2$

Self-weight of the slab according to calculated depth

S – Exposure class related to environmental conditions Another parameters:

Z – Working life of the structure



Task 1 – Assignment goals


Our goal will be to:

- Design the dimensions of all elements.
- Do detailed calculation of 2D frame calculation of bending moments, shear and normal forces using FEM software.
- Design steel reinforcement in the 1st floor members:
 - beam,
 - column.
- Draw layout of the reinforcement.

Bending beam reinforcement


Cross-sections

We have designed reinforcement in 3 cross-sections. Now we must decide, where to "stretch" the reinforcement bars (rebars).




Locations of reinforcement

Rebars MUST be on the side of the beam where the bending moment is (because this is where tension is).



Bending moments envelope

First, we will take the moments envelope from IdeaStatica and copy it to AutoCAD.




HOW?


- Printscreen the moment curves in IdeaStatica, insert them to model space in AutoCAD, and adjust to the desired scale.
- Draw "spline" lines using the IdeaStatica curves as a background.

Adjusted envelope

Reduce support moments to values in the face of the column (like in HW3).



Shift the envelope by $a_l = \frac{z}{2} \cot \theta$.




Lever arm of internal forces (see HW3).Shear crack angle (see HW3).

Adjusted envelope


Why is the shift necessary?

- Shear stresses are perpendicular to shear cracks.
- Shear force has vertical and horizontal part.
- Stirrups are vertical \rightarrow horizontal part of shear force is carried by bending reinforcement.




Rebar length


Divide the design bending moment by the number of rebars designed for the cross-section.



Using this division, we can obtain "needed" length of each rebar.




However, rebars must be in pairs (except for the last one, if you have odd number).




Why?


However, rebars must be in pairs (except for the last one, if you have odd number).



Why? Because every cross-section must be reinforced symmetrically.

Moreover, each rebar must be "anchored" beyond the moment envelope using the *minimal anchorage length* $l_{b,min}$ and *design anchorage length* l_{bd} .





The length required to transfer a force from a rebar to the surrounding concrete.

This is how we get the final required length of the rebars.

Anchorage length

We need to calculate the minimal and design anchorage length, but first, we need the basic anchorage length

$$l_{b,req} = \frac{\varnothing_s}{4} \times \frac{\sigma_{sd}}{f_{bd}},$$

where \varnothing_s is the rebar diameter,

 σ_{sd} is the stress in the reinforcement (assume f_{vd}),

 $f_{bd} = 2.25n_1n_2f_{ctd}$, (bond stress between the rebars and concrete)

where $n_1 = 1.0$ for good rebar position*,

 $n_1 = 0.7$ for other rebar positions,

 $n_2 = 1.0$ for $\varnothing_S \le 32$ mm,

 $n_2 = (132 - \varnothing_s)/100$ for $\varnothing_s > 32$ mm,

 $f_{ctd} = f_{ctk,0.05}/1.5$, (for $f_{ctk,0.05}$ see table of concrete strengths).



Anchorage length

Using the basic anchorage length, we can calculate the minimal anchorage length

$$l_{b,min} = \max(0.3l_{b,req}, 10\emptyset_s, 100 \text{ mm}),$$


and the design anchorage length

$$l_{b,d} = \max(\alpha_1 \alpha_2 \alpha_3 \alpha_4 \alpha_5 l_{b,req}; l_{b,min})$$


where α_i are coefficients expressing influence of shape of the end of rebars, cover depth, transverse unwelded rebars and transverse pressure (you can assume $\alpha_i = 1.0$).

Anchorage length

For bottom reinforcement, at least two bars must be extended at least 10ø behind the face of the column.




We must draw this scheme for all supports and mid-spans.



In the left mid-span (where you didn't design reinforcement) assume the same reinforcement as in the right span.

In the left support assume the same reinforcement as in the right support.


Using the schemes, we can design the rebar length.



Shear beam reinforcement

Shear beam reinforcement

Shear beam reinforcement (including its positions) was already designed in HW3. Use the values from this homework.



Column shear reinforcement (column ties)

Column ties


In column, we have designed only the vertical reinforcement in HW4. However, we must also design column ties, which prevent buckling of reinforcement.

Diameter: $\varnothing_{\text{tie}} \ge \max\left(\frac{\varnothing_{\text{s}}}{4}; 6 \text{ mm}\right)$

Diameter of vertical column reinforcement


Basic spacing: $s_1 \le \min(20\emptyset_s; \min(b_{col}; h_{col}); 400 \text{ mm})$

Spacing in lapping area and below and above beam (in the distance of $\max(b_{col}; h_{col})$): $s_2 \le 0.6s_1$



Work joints

After concreting of 1st floor, you have to wait some time before concrete the 2nd floor. Therefore, column vertical reinforcement is not continual over all floors but only on one floor, and individual rebars from each floor must be connected by lapping.



Lapping length

Equation for lapping length is very similar to equation for anchorage length. The equation is:

$$l_{0,d} = \max(\alpha_1 \alpha_2 \alpha_3 \alpha_5 \alpha_6 l_{b,req}; l_{0,min})$$



where

The length required to transfer a force from one rebar to another rebar.

 $l_{b,req}$ is the same as for anchorage,


$$l_{0,min} = \max(0.3\alpha_6 l_{b,req}, 15\emptyset_s, 200 \text{ mm}),$$

$$\alpha_6 = 1.5$$

Tie (stirrup) ends

We need to close the tie.

The closing end length can be estimated as 10x the tie diameter.



This is also true for beam stirrups!

Example drawings

Example 1 (with commentary)

5400 SECTION A-A (1:20) 5800 4900 4900 4500 4500 ST. Ø6 à 190 mm SECTION B-B (1:20) ☐TIE Ø6; L=1500 mm (3)ST.Ø6;L=1900 mm 400 (0) T.R.2xØ12;L=5800 mm ③ T.R.2xØ12;L=4900 mm T.R.2xØ12;L=4900 mm SECTION C-C (1:20))1xØ16;L=2090 mm 3 2xØ16;L=3640 mm 3 2xØ16;L=3640 mm ① 1xØ16;L=2090 mm (4) 2xØ16;L=10970 mm 2 2xØ16;L=2610 mm 2xØ16;L=3520 mm M_=78,03 kNm M_=78,03 kNm SECTION D-D (1:20) M_{ed}=108,15 kNm \$ 2xØ12;L=5740 mm (5) 2xØ12;L=5740 mm 7 2xØ16;L=6300 mm ② 2xØ12;L=4830 mm (8) 1xØ16;L=4670 mm 6 2xØ12;L=4830 mm

(the curve must be SYMMETRIC in our structure)

Layout of moments

Longitudinal section

+ shapes of rebars

Notes

MATERIALS: CONCRETE C20/25 STEEL B500B

COVER DEPTH 25 mm


AXIAL DIMENSIONS OF REBARS

| | FRAME REINFORCEMENT DRAWING | | CST2 |
|---|-----------------------------|------------|----------|
| | Prepared by: JÁRA CIMRMAN | WT 1910/11 | R-28 |
| 5 | Checked byl: prof. KLOKNER | 1:50 | FSV ČVUT |


Drawing Title

Sections


Example 1



Example 2



Example 3





thank you for your attention

Recognitions

I thank **Assoc. Prof. Petr Bílý** for his original seminar presentation and other supporting materials from which this presentation was created.